

CONCRETE AND CONSTRUCTIONAL ENGINEERING

INCLUDING PRESTRESSED CONCRETE

SEPTEMBER, 1953.



Vol. XLVIII, No. 9

FORTY-EIGHTH YEAR OF PUBLICATION

PRICE 1s. 6d.

ANNUAL SUBSCRIPTION 18s., POST FREE. \$3.90 in Canada and U.S.A.

LEADING CONTENTS

	PAGE
A Book by M. Le Corbusier	287
The Application of Reinforced Concrete to School Buildings. By Felix J. Samuely	289
Book Reviews	302
A Graphical Method of Designing Cylindrical Shells. By Professor A. L. L. Baker	303
Reinforced Concrete Flats in South London	307
A Cylindrical Prestressed Concrete Tank	310

No. 550.

ISSUED MONTHLY

Registered for
Canadian Magazine Post

BOOKS ON CONCRETE

For catalogue of "Concrete Series" books on concrete and allied subjects, send a postcard to:

CONCRETE PUBLICATIONS LTD., 14 DARTMOUTH ST., LONDON, S.W.1



For over 60 years

this trade mark has stood for speed and
strength in reinforced concrete work.

DRAGON

(Brand)

PORTLAND CEMENT

Supplied by

THE SOUTH WALES PORTLAND CEMENT & LIME CO. LTD.
PENARTH, SOUTH WALES


Telephone : Penarth 300

Telegrams : "Cement, Penarth"

Burton's

TUBULAR STEEL TRENCH STRUTS

(ADJUSTABLE)



OUTSTANDING ADVANTAGES

- 1.—Save at least 80% labour by eliminating the old-fashioned system of cutting, wedging and nailing timber strutting; no waste of timber.
- 2.—Fixed by one man in one minute.
- 3.—Being steel complete, they are practically everlasting and can be used over and over again indefinitely.
- 4.—Take up very little store space and very compact for transport.
- 5.—No loose parts which can be lost, so they are always ready for work.

IN THREE SIZES

Size No.	Length		Approx. Weight
	Closed	Expanded	
1.	1' 6"	2' 3"	14 lb.
2.	2' 4"	3' 6½"	19 lb.
3.	3' 4"	5' 6"	24 lb.

Burton's Patent Solid Dropforged Steel Scaffolding Fittings

THE LONDON & MIDLAND STEEL SCAFFOLDING CO., LTD.

ST. LUKE'S WORKS, OLD HILL, STAFFORDSHIRE

Telegrams: DUBELGRIP, CRADLEY HEATH.

Telephone: CRADLEY HEATH 6237/8

London Offices: BURWOOD HOUSE, CAXTON STREET, S.W.1

Telephone: Abbey 6483/4.

Telegrams: Dubelgrip, Sowest, London



BUILT BY
THE

YORKSHIRE HENNEBIQUE

CONTRACTING CO. LTD.

VIADUCT WORKS,
KIRKSTALL ROAD,

Telephone: Leeds 20687-8-9
Telegrams: Ferro, Leeds, 4

We Built the first REINFORCED CONCRETE Silos in this country

Telephone: Hull 33501

Telephone: Dundee 6170

Branch Offices:

30. Wincolmllee, HULL
Western Wharf, DUNDEE

Concrete paving for roads and runways



Central weighbatching plant

The most up to date airfield and road construction equipment in the world is available backed by experience and an efficient organisation.

The construction of this new airfield requires 500,000 cubic yards of high quality concrete which is controlled at every stage of production.

Mobile paving units mix and place the concrete at the point of operation at a rate of 10,000 cubic yards a week. The dry batches of materials for the concrete are accurately proportioned by weight at the central batching plant and transported to the pavers.



The two mobile pavers are followed by a spreader, two finishing machines and a joint cutter

Contractors for every class of Building and Civil Engineering at home and overseas

John Laing and Son Limited, London, Carlisle, Johannesburg and Lusaka. Established in 1848


POWER BAR BENDERS

FOR ALL SIZES OF REINFORCING BARS


STANDARD PRODUCTION MODELS

The ARD. 50 MODEL—as illustrated on right—has a capacity for cold bending Mild Steel Bars up to 2" dia. and incorporates a second Bending Head to give high-rate bending for small diameter bars.

The RAS. 40 MODEL shown below is a single disc machine of exceptional performance. With a capacity for $1\frac{1}{2}$ " dia. bars, it bends at highest practical rate—e.g. a full hook takes only 3 seconds bending time.



*Ensure accuracy, economy
& simplicity of operation*



INTERESTING FEATURES

Either of the Models illustrated can be supplied motorised or engine driven.

Standard Accessories supplied include all necessary Formers and Bending Pins, a special Backrest for simultaneous bending of a number of small diameter bars, and Accessories for forming right-angle loops in one operation.

Special Safety Device incorporated to prevent damage to mechanism if overloaded.

The desired Bending Angle may be set mathematically, and this is of great assistance in Repetition Bending.

CEMENT & STEEL LTD.

SECOND AVENUE

CHATHAM

KENT

Telephone : Chatham 45580

Telegrams and Cables : Cembelgi, Chatham

Determining the cover of reinforcement, or the position of prestressing cables, immediately the concrete is placed avoids risk of unsafe structures . . .



The following is an extract from a letter received from a user of the C. & C.A. Covermeter regarding the illustration shown above—"I enclose a print of a reinforced concrete cantilever step that failed due to incorrect positioning of the reinforcing steel. Being one of a long double-flight staircase concern was felt for the safety of the other steps. The Covermeter was used, and they were all found to be unsafe in various degrees, necessitating cutting out and renewing. The new steps were checked by Covermeter before being built in."



C. & C.A. COVERMETER

The Cement and Concrete Association Covermeter, illustrated above, has been specially produced to provide an easy, accurate, and economical means of finding the exact cover of reinforcement bars, or the position of prestressing cables, without interfering with the concrete and before the concrete has hardened. It thus enables Reinforced Concrete Engineers to make sure that the specified cover of reinforcement is maintained throughout the structure, and that the position of prestressing cables is in accordance with the design. It can also be used to find the position of reinforcement, gas pipes, and other fittings in existing structures. The C. & C.A. Covermeter can be supplied for Metric or Imperial systems of measurements. For full details and prices, send to the manufacturers:

B. & P. RADIOS LIMITED

(ELECTRONIC DIVISION), LANGHAM PARADE, LONDON, N.15. Tel.: Bowes Park 7140



*There is no doubt
about the advantages
of Tempered Presdwood
for the lining of
Concrete Forms . . .*

It has been used extensively—everywhere—
since 1930, and is recognised as the best
sheet hardboard.

Registered Trade Mark



Write for illustrated Technical Catalogue.

Masonite Ltd., Bevis Marks, London, E.C.3
Avenue 2846

GUNITE SPECIALISTS

**W.M. MULCASTER
& CO. (CONTRACTORS) LTD.**

We invite inquiries for Gunité Linings and Renderings
for new or old structures of every kind in any part
of the country.

HASLINGTON


CREWE

Telephone: Crewe 2265-6.

HOLST

& CO LTD

CIVIL ENGINEERING CONTRACTORS, REINFORCED CONCRETE



BUNKER AT NANTGARW FOR THE NATIONAL COAL BOARD

REINFORCED CONCRETE DESIGN AND
CONSTRUCTION BY HOLST & CO. LTD

Head Office :

NETHERFIELD, BERKHAMSTED, HERTS.

Telephone : Berkhamsted 1128-30

Branches : LONDON, BIRMINGHAM, MANCHESTER, LEEDS, DURHAM, EDINBURGH, CARDIFF

MAKE IT A *FAST* JOB WITH MILLFRAMES



Horizontal tube inserted in Millframe Coupler. Half-turn the spring steel plate, tighten bolt—it's fast!

Going up. The next Millframe slides quickly into position on verticals of the H-FRAME below.

Half-turn plate, tighten bolt. Millframes are then secured to give standard lift height of 6'.


Millframes of special light-gauge steel tube give high speed erection and dismantling.

MILLS SCAFFOLD CO. LTD.

(A Subsidiary of Guest, Keen and Nettlefolds, Ltd.)

Head Office: TRUSSLEY WORKS, HAMMERSMITH GROVE, LONDON, W.6. (Riverside 5026/9)

Agents and Depots: BELFAST • BIRMINGHAM • BOURNEMOUTH • BRIGHTON • BRISTOL • CANTERBURY • CARDIFF
COVENTRY • CROYDON • DUBLIN • GLASGOW • HULL • ILFORD • LIVERPOOL • LOWESTOFT • MANCHESTER
NEWCASTLE • NORWICH • PLYMOUTH • PORTSMOUTH • READING • SHIPLEY • SOUTHAMPTON • SWANSEA • YARMOUTH



REINFORCED CONCRETE PURIFIERS
FOR THE EASTERN GAS BOARD
AT PONDERS END WORKS

PETER LIND & CO LTD


ROMNEY HOUSE, TUFTON STREET, LONDON, S.W.1

TELEPHONE: ABBEY 7361 (10 lines)

GIANT

pneumatic vibrator

INVALUABLE FOR
LARGE AGGREGATE
AND LOW
WATER/CEMENT
RATIO



The 4-in. head of this GIANT internal pneumatic vibrator (frequency 9,000 r.p.m.) is designed specially for placing large volumes of concrete of large aggregate and low water/cement ratio which could not be placed by smaller vibrators. It is strongly constructed, easy to use, and will withstand heavy wear and tear. It is an indispensable vibrator for heavy foundations, sea walls, dams, etc. For full details, send to:

COMPACTORS ENGINEERING LTD

Also suppliers of all sizes of electric, pneumatic, and petrol-engine driven internal vibrators, bar-benders and croppers, concrete distributors, vibro-finishers, vibro joint-cutters, central mixing plants, Vibrosoil compactors, trench compactors.

65 EFFRA ROAD, LONDON, S.W.2.

TELEPHONE: BRIXTON 4031-3

...leading Authorities

endorse

EVODYNE CHLORINATED RUBBER PAINTS

because

They give the highest practical degree of protection to iron, steel and wood against acids, alkalis, corrosive gases, artificial fertilizers and salt water

and

can be successfully applied to alkaline surfaces such as asbestos cement sheeting, concrete and plaster, without special primers.



TELEPHONE HOUSE,
MANCHESTER

Evodyne (Chlorinated Rubber) Paint Light Biscuit BS.381c two coats applied to concrete surfaces of the building for the Ministry of Works.

Contractors :

Messrs. Arthur Wardle Ltd.,
30 Albert Street, Manchester, 3.

Evodyne Paints are easily applied by brush or spray-gun and are dust dry in 30 minutes. A gallon covers up to 60 square yards on primed metal and up to 40 square yards on porous surfaces. Available in our own range of colours, or in any B.S.S. 381c. colour.

Send for Colour
Chart and Leaflet
1003 for full
information.



EVODYNE CHLORINATED RUBBER PAINTS

Decorative . . . Economical . . . Long Lasting


EVODE LIMITED, Glover Street, Stafford, England

Telephone: 1590/1/2

Telegrams: Evode, Stafford



**If
you've
a
WATER
LEAKAGE
problem**



The Cementation process is now being extensively used in sealing off leakages of water from large tanks, docks and other similar structures, and in rendering watertight tunnel linings. Contracts of this nature have been carried out for the South Metropolitan Gas Works, the Gas Light and Coke Co., the Meltham U.D.C. where escapes of water were occurring from the gasholder tanks, at the Burry Port Dock of the G.W.R. Barry Dock, and Leeds Electricity Works Canal, where loss of water through the walls and floors of the structure was becoming serious. Similarly, cementation has been employed in rendering watertight the swimming baths at Clifton, Bristol, and Bradford-on-Avon, and the sewage disposal tanks for the Doncaster Corporation. It has also been used for waterproofing of basement walls and floors as at the new B.B.C. House, London, Stockport Sewage Works, Grimsby Power Station, and for many other purposes.

consult *The* **C**EMENTATION
COMPANY LIMITED

BENTLEY WORKS, DONCASTER. Telephone : DONCASTER 54177-8-9



TELECRETE

LIQUID CONCRETE TIPPER

**The
ideal method
of transporting
concrete from
a central
mixing plant**



Designed specially for big contracts, the Telecrete Concrete Tipper has proved an economical factor in speeding up the handling of concrete, with savings in labour costs and time. It is sturdily constructed, easy to operate, and will withstand heavy wear and tear. Ideal for concrete roads, runways, sea walls, factories with large floor areas, and other contracts involving the use of large volumes of concrete. Let us send you full particulars.

Write for illustrated details:

TELEHOIST LIMITED

TELEHOIST WORKS, Swindon Lane, CHELTENHAM, GLOS.
TELEPHONE: Cheltenham 53254-5-6 and 55152. TELEGRAMS: Telehoist, Cheltenham.

SUPER CEMENT

'SUBMARINE BRAND'

THE TANNO-CATALYSED PORTLAND CEMENT

SAVES TIME

SAVES TROUBLE

NATURALLY WATERPROOF, CONTAINS NO WATER REPELLENT MATERIAL

Uses:—

For CONCRETE

Provides a CONCRETE of great strength at early dates and impervious to water, oil, etc., without any form of surface coating.

For PAVING

Produces a hard wearing PAVING, dustless and proof against penetration by water, etc.

For RENDERING

Supplies an impenetrable RENDERING of such adhesive power that a 1" thickness will resist an outside pressure of at least a 20' head of water.

For SLURRY (as paint)

Makes a perfectly watertight covering to brick or breeze concrete walls at very small cost, and also provides the best watertight undercoat to coloured finishes.

Technical Information is available to users.

Used in 1914-1918 and still used by:

Air Ministry, War Office, Admiralty, Ministry of Works, Ministry of Supply, etc.

SUPER CEMENT LTD.,

29 TAVISTOCK SQUARE, Phone 1
LONDON, W.C.1 Euston 1808

**CONCRETE
PROOFING
Co. LTD.**


**GUNITE
SPECIALISTS**

Expert advice and schemes submitted for gunite work of every kind. Complete information on the various uses of gunite will be gladly sent on request.

96, Victoria Street, Westminster, S.W.1

Telephone:
VICTORIA 7877 and 6276

GAMMON-MORGAN WATER ESTIMATOR



The most accurate, simple, and rapid means of measuring the water content in the sand. No weighing or chemicals are required, and an adequate sample is used. The GAMMON - MORGAN WATER ESTIMATOR should be available alongside every mixer, so that the water content of every mix may be correctly gauged. Full details will be sent on request.

MOISTURE VARIATIONS IN THE SAND

★ Engineers should specify that the concrete mix shall be adjusted for moisture variation in the sand, so that the total water in the batch shall consist of the water carried in the aggregates plus the water added in the mixer.

PRICE £3 3. 0. each (9 Canadian or U.S. dollars)
CARRYING CASE £1 11s. 6d. (4.62 Canadian or U.S. dollars)

COLCRETE LTD.

GUN LANE, STROOD, ROCHESTER, KENT

TELEPHONE: STROOD 7334 and 7736. TELEGRAMS: GROUTCRETE, ROCHESTER

- **Reinforced Concrete**

DESIGN AND CONSTRUCTION

- **Floors**

IN SITU AND PRECAST

- **Staircases**

- **Cast Stone**

- **Granolithic Pavings**

- **Duromit Pavings**

(In association with the Kleine Co. Ltd.)

STUART'S

GRANOLITHIC CO. LTD.

FOUNDED 1840

LONDON

105 Baker Street, W.1.

Telephone: Welbeck 2525/6.

BIRMINGHAM

Northcote Road, Stechford.

Telephone: Stechford 3631/2.

EDINBURGH

46 Duff Street.


Telephone: Edinburgh 61506.

MANCHESTER

Ashton Road, Bredbury, Stockport.

Telephone: Woodley 2677/8.

In Turkey, too — **RAPID METAL** *Formwork* is right on the job!



Slurry Silos for **CEMENT FACTORY** at IZMIR

go up faster, better and cheaper, thanks to


RAPID METAL SHUTTERING

The main contractors decided to use Rapid Metal Formwork to assist them in maintaining an exacting progress schedule. These pictures show how simple it is to erect **RAPID METAL** self-aligning steel shuttering. Native labour was employed, without demonstration by us, the only guidance being the disposition drawings supplied with the shuttering.

MAIN CONTRACTORS:

Brathwaite & Co. (Engineers) Limited.

CLIENT: *Izmir Cimento Fabrikasi, T.A.S.*



Patentees and sole manufacturers:

**RAPID METAL
DEVELOPMENTS LTD.,
209 Walsall Rd.,
Birmingham, 22b**

Telephone: Birchfields 6021

*London Office: 47 Victoria St.,
S.W.1 Tel: Abbey 4077*

*South Wales Depot:
Bridge Road, Waunarlwydd,
Swansea. Tel: Gowerton 77*

You can depend on

RAPID METAL
Formwork





WATES
at WORK

*New block of flats for London
County Council at Clarence
Avenue, Wandsworth*

WATES BUILD

Wates Ltd., BUILDING &
CIVIL ENGINEERING CONTRACTORS

1258-1260 London Rd., London, S.W.16.

Telephone: POLLARDS 4401 (15 lines)

use the **A.B.** **SERVICE** **for concrete work**

SHUTTER PANELS

All sizes and types

ADJUSTABLE SHORES

for floor and beam support

ADJUSTABLE CENTRE FORMS

for floor support

SHUTTERLOCK WALING CLIPS

for bracing with scaffold tube and locking the panels together, eliminating nuts and bolts in shuttering. Tremendous saving in erecting and striking costs

COLUMN CLAMPS : BEAM CLAMPS

ROAD FORMS : TRENCH STRUTS

We also design and manufacture Steel Moulds for Floor Beams, Piles, Railway Sleepers and all other precast concrete products

Let us solve your problems

A. B. MOULD & CONSTRUCTION CO., LTD.

42 WHITEHORSE ROAD

CROYDON

SURREY

Telephone : Thornton Heath 4947.

Telegrams : Abmould, Croydon.

WORKS: VULCAN WAY, NEW ADDINGTON, SURREY

a job for the specialist




*REINFORCED CONCRETE SILOS AND
MALTINGS FOR GILSTRAP EARP &
CO. LTD., LOUTH*

ARCHITECTS: GELDER AND KITCHEN, HULL

Mitchell CONSTRUCTION COMPANY

WHARF WORKS, PETERBOROUGH

London Office: 7 Gower Street, W.C.1



When all is done and the traffic begins to roll, not the smooth fine surface but the inner strength will tell whether this is a road to last, a road to do credit to its makers . . . No better way to ensure even hydration of concrete, sound setting and all-through strength than the underlay of moisture-impermeable IBECO that is fast becoming standard practice . . . It's an economy too, and a precious saver of man-hours.

IBECO




COMPLETELY WATERPROOF CONCRETING PAPER

MADE BY C. DAVIDSON & SONS LTD · MUGIE MOSS · ABERDEENSHIRE



1000 ft. of Prestressed Concrete Culvert



Engineer to the Lee Conservancy Catchment Board: M. Nixon, M.B.E., B.Sc., A.M.Inst.C.E.
Prestressed concrete beams made by Shockcrete Products Ltd. for the main contractors, Concrete Piling Ltd.

As part of the flood relief scheme of the Lee Conservancy Catchment Board in the valley of the River Lee, a new channel is being constructed, of which about one half is to be a culvert decked by Lee-McCall prestressed concrete beams. There are 512 beams, each having an overall length of 57 ft., giving a clear span between the walls of the culvert of 53 ft. 5 in. The beams are of I-section, 30 in. deep by 24 in. wide, each containing three 'MACALLOY' bars of $1\frac{1}{8}$ in. dia. After the beams have been placed in position, they are prestressed transversely in bays 20 beams wide, by ten $\frac{7}{8}$ in. dia. 'MACALLOY' bars.

Particulars are given in Bulletin No. 2 which is available on request.

PRESTRESSED CONCRETE



McCALLS MACALLOY LTD.

TEMPLEBOROUGH SHEFFIELD

... it's

KWIKFORM

REGD. TRADE MARK

... Specialisation in
concrete formwork

The Two-Component System
... without equal for safety,
speed of erection and dis-
mantling. No other system
can guarantee so little deflec-
tion without propping.



Suspended Formwork

Shell Roof Construction is simpli-
fied by the use of 'Kwikform'
Flexible Formwork. Minimum
constructional time—true clean
soffit—maximum unobstructed
working space—adaptability to
any radius above 3 ft.—absolute
rigidity of formwork.




Flexible
Formwork




Wall Formwork

The Adaptable Concrete Form-
work. Designed for use in the
widest possible range for double or
single facework; columns; beams;
piers; battered retaining walls, etc.



The illustration shows Flexible Formwork in position to receive reinforcing.



Circular Tank construction is simple, speedy and economical when Flexible Formwork is used. Illustration is by courtesy of Preload (G.B.) Ltd.

Descriptive literature of all 'Kwikform' equipment available on request. SALE or HIRE

Patents granted and pending in all principal countries of the world.

KWIKFORM LTD.

KWIKFORM LTD., WATERLOO ROAD, BIRMINGHAM, 25.

London Office : 66 Victoria Street, S.W. 1.



Ruberoid C. and E. Jointing provides the necessary resilience to allow concrete structures of all types to move under temperature variations without building up dangerous stresses. Where a 'single operation' material is required Ruberoid C. and E. Jointing can be relied upon to give complete satisfaction. Available in lengths up to 6 ft., thicknesses from $\frac{3}{8}$ to 1 in. and depth to suit the concrete. Use Ruberoid, the original Concreting Paper, in the road bed. It prevents absorption of liquid cement into the sub-base and aids free movement of the slab.

a product of:

THE RUBEROID COMPANY LTD.,

187, COMMONWEALTH HOUSE, NEW OXFORD STREET, LONDON, W.C.1



C.E.113



DELIVERED DIRECT TO ANY
CONTRACT BY MOTOR LORRY.

Quotations on Application.

Telephone: Paddington 2024 (3 lines).

WASHED
BALLAST, SAND, SHINGLE &
Crushed Aggregate for Reinforced Concrete.

WILLIAM BOYER & SONS, LTD.

Sand and Ballast Specialists,

**IRONGATE WHARF,
PADDINGTON BASIN, W.**

MEMBERS OF B.S. & A.T.A.

BARS for REINFORCEMENT

BARS in sizes from $\frac{7}{32}$ in. to $\frac{3}{16}$ in. Mild Steel 28/33 T.T. cut to lengths.


BARS bent to schedule.

BARS for prompt delivery to site at competitive prices.

Send your inquiries to

PASHLEY & TRICKETT · LTD.

STEVENSON ROAD, SHEFFIELD, 9. Telephone: 41136-7. Telegrams: "PET" SHEFFIELD, 9.



reinforced concrete stores

This reinforced concrete stores has been built at Derby for the Railway Executive Midland Region. The building is a two-story construction erected on piled foundations and consists of nine bays of barrel-vault roof each of which is 67 ft. 6 in. long between the centres of stiffening ribs. Each bay has a 45-ft. span and the shell thickness varies between $2\frac{1}{2}$ in. and $3\frac{1}{2}$ in. over the stiffening ribs.

Specialists in all types of reinforced concrete structures for industrial and public authorities.

Contractors to :—

ADMIRALTY
WAR OFFICE
MINISTRY OF SUPPLY
MINISTRY OF WORKS
BRITISH ELECTRICITY AUTHORITY
DOCKS & HARBOUR BOARDS
RIVER & DRAINAGE AUTHORITIES
RAILWAYS & INLAND WATERWAYS
SHIPBUILDING & HEAVY ENGINEERING
INDUSTRIES.

CONCRETE PILING LIMITED

10 WESTMINSTER PALACE GARDENS, ARTILLERY ROW, LONDON, S.W.1 Abbey 1626 7.

LADAS DRIVE, BELFAST Belfast 58100. WORKS: RIVER ROAD, BARKING Rippleway 2624.



HUMDINGER VIBRATOR

HIGHER FREQUENCY - LOWER PLACING COSTS

Will deal easily with so called "no-slump" mixes, e.g., 1:2:4 mix, 0.5 water-cement ratio, or 1:1½:3 mix, 0.4 water-cement ratio. The Humdinger's 11,500 vibrations-per-minute compact quicker and can save money on every cubic yard of concrete placed. The co-axial positive drive gives a flexible shaft speed of only 2,500 r.p.m.—ensuring long, constant use between routine overhauls. Petrol motor (with centrifugal idling clutch), or electric drive. For all grades of concrete, use an ACE Humdinger. Please write for more information.



- Lowest cost per yard
- Better concrete
- Faster placing
- 10,000/12,000 v.p.m.




A.C.E. MACHINERY LTD.



VIBRATOR DEPT., PORCEN RD., BRIXTON, LONDON, S.W.2. Tel: BRixton 3293



CHRISTIANI & NIELSEN



Extensions to Sewage Works for Burnley Corporation. Borough Engineer & Surveyor :
A. G. Richardson, Esq., A.M.Inst.C.E., M.I.Mun.E.

**CHRISTIANI & NIELSEN LTD., ROMNEY HOUSE, TUFTON STREET,
LONDON, S.W.1**

Telephone : ABBey 6614-7

ALSO OFFICES AT: Aarhus — Asuncion — Bahia
Bangkok — Buenos Aires — Cape Town — Caracas
Copenhagen — Durban — Guayaquil — Hamburg
Helsingfors — Lima — Lourenco Marques — Mexico City
Montevideo — New York — Oslo — Paris — Rangoon
Rio de Janeiro — Sao Paulo — Stockholm — The Hague



MOULD OILS & COMPOUNDS

for every process of
concrete production

CONCREAM

This non-staining, smooth and easy working white mould oil can be used with confidence on all classes of in situ and precast concrete work where the use of a white mould oil is recommended.

VIBRAMOL

This non-staining and non-separating mould oil is made specially for use on steel shuttering and moulds where vibrators are used, and provides a good film which is not readily moved under vibration.

SPRAYMOL

This grade of mould oil has been specially produced for use with a spray gun. It can be used with great economy on all types of shuttering and moulds, and will not separate under pressure.

"P.S."

Experience has shown that the production of precast and in situ prestressed concrete needs a special mould compound, and in collaboration with leading prestressed specialists we have produced Grade "P.S." Mould Compound for this class of work.

"8.A."

This Mould Compound has been specially produced to satisfy the requirements of those engaged in the production of spun concrete products.

CONCREAM Regd.
VIBRAMOL Regd.
SPRAYMOL Regd.
"P.S." & "8.A."

**PRODUCTS OF THE
ORIGINAL MAKERS OF
CONCRETE MOULD OILS**

We specialise in the production of mould oils and compounds for concrete work of every kind, from mass concrete work to high-class architectural stone work, and have an unrivalled experience which enables us to give expert advice on all mould oil problems. We have a grade for every purpose, and will be pleased to submit full details, samples, and prices on request.

RICH^d HUMBLE & SON, LTD., COLUMBA OIL WORKS, LEEDS, 3

Telephone : 27155.

ESTABLISHED 1854.

Telegrams : "Columba, Leeds, 3."

FRAMEWELD

Trade Mark

Patent No. 539265

IT STANDS ALONE

*Prefabricated
Welded Reinforcement
saves
TIME
MONEY
LABOUR*

DESIGN · FABRICATION · ERECTION

T.C. JONES

& CO. LTD

Reinforcement Specialists

1903-1953 Fifty Years of Service to Industry

WOOD LANE, LONDON, W.12. Tel: Shepherds Bush 2020


BUTE STREET, CARDIFF.

Tel: Cardiff 28786

TREORCHY, GLAMORGAN.

Tel: Pentre 2381

THE
600
GROUP
OF COMPANIES



An Electrically Driven PC4 Concrete Pump.
Capacities from 8 to 10 cu. yds. per hour.
Ranges actually obtained 125 ft. vertical or
1,500 ft. horizontal.

CONCRETE BY PUMP AND PIPELINE

- The latest and most efficient method of placing concrete.
- Pump and Mixing plant can be located where it is most convenient for storing and handling aggregates and cement.
- The concrete is delivered by pipeline just wherever it is required with the minimum of interference with the building operations.
- The speed of the pump governs the whole of the concreting gang.
- Pumpable concrete must of necessity be good concrete.



THE REGISTERED TRADE MARK OF
THE CONCRETE PUMP COMPANY LIMITED

THE CONCRETE PUMP COMPANY LTD

4 STAFFORD TERRACE, LONDON, W.8

Telephone: Western 3546.

Telegrams: Pumpcret, Kens, London.

DOUGLAS

builds *from first to last*

This photograph shows part of the impressive Administration Block comprising laboratory, staff canteens, locker rooms and medical wing, recently constructed for a major national industrial undertaking. Architects: Sir Percy Thomas & Son.

ROBERT M. DOUGLAS (CONTRACTORS) LTD.

395 George Road, Birmingham 23.
Bridge Road, Waunarlwydd, Swansea.
47 Victoria Street, London, S.W.1.



● CIVIL ENGINEERING • BUILDING • SITE INVESTIGATION • EXCAVATIONS
FOUNDATIONS • REINFORCED AND PRESTRESSED CONCRETE • FACTORIES
ROADS • BRIDGES • PILING • SEWERAGE • RAILWAYS • WATERWAYS
TUNNELS

POWER!

for
Industrial
Purposes



ENGINE 12 HOURLY RATINGS

- 933 cc. PETROL (4 cyl.)
8 B.H.P. @ 1500 R.P.M.
13.75 B.H.P. @ 2500 R.P.M.
- 1172 cc. PETROL (4 cyl.)
11.5 B.H.P. @ 1500 R.P.M.
19 B.H.P. @ 2500 R.P.M.
- 1508 cc. PETROL (4 cyl.)
17 B.H.P. @ 1500 R.P.M.
28 B.H.P. @ 2500 R.P.M.
- 2262 cc. PETROL (6 cyl.)
24 B.H.P. @ 1500 R.P.M.
40 B.H.P. @ 2500 R.P.M.
- 3621.5 cc. PETROL (V-8 cyl.)
34 B.H.P. @ 1500 R.P.M.
56 B.H.P. @ 2500 R.P.M.
- 3260 cc. PETROL (4 cyl.)
22 B.H.P. @ 1000 R.P.M.
35.5 B.H.P. @ 1600 R.P.M.
- 3610 cc. VAPORISING OIL (4 cyl.)
22 B.H.P. @ 1000 R.P.M.
34.5 B.H.P. @ 1600 R.P.M.
- 3610 cc. DIESEL (4 cyl.)
22 B.H.P. @ 1000 R.P.M.
36 B.H.P. @ 1600 R.P.M.

Now a great new star joins the range of Ford Industrial Units — an entirely new 4-cylinder diesel engine capable of maintaining 34 B.H.P. continuously at 1500 R.P.M.


Full details of this and all other engines in the range are obtainable from our Industrial Units Dept.



BY APPOINTMENT MOTOR
VEHICLE MANUFACTURERS TO
THE LATE KING GEORGE VI

FORD MOTOR COMPANY LIMITED • DAGENHAM • ESSEX

**ANOTHER
ANGLIAN
PRESTRESSED
PRODUCT**



Hams Hall Power Station, Birmingham. Road-over-Rail bridge for B.E. Authority. Consulting Engineers:—Mouchel & Partners, Ltd. Contractors:—Sir Robert McAlpine & Co. (Midland), Ltd.

● PYLONS

● PILES

● SHEET PILES

● ROAD AND RAIL BRIDGES

● ROOF AND FLOOR BEAMS

**PRESTRESSED
BEAMS ON
ROAD OVER RAIL
BRIDGE**



ANGLIAN BUILDING PRODUCTS LTD.
LENWADE 15, NORWICH. TELEPHONE: GT. WITCHINGHAM 291

GLASCRETE for SHELL ROOFS

Shell roofs can be efficiently lighted by simply placing precast GLASCRETE panels on the shuttering and casting in monolithic with the roof, thus saving time and labour in trimming openings.

Panels are cast to the curve of the roof and anchor bars are left protruding from the frame for bonding to the roof slab.




Factory, London.

Architects : Messrs. Clifford Tee & Gale.

Telephone : CEN. 5866
(5 lines)

J. A. KING & Co. LTD.,
181, QUEEN VICTORIA ST., LONDON, E.C.4.

CONCRETE REINFORCEMENT



We carry large stocks of M.S. and High Tensile Steel, which can be supplied cut to lengths, hooked and bent in accordance with schedules, or in random stock lengths, from our Stock-holding Department.

We specialise in Large projects, for which our Designers are always at your service.



FOR ALL CONSTRUCTION PURPOSES

SOMMERFELDS LTD.

WELLINGTON • SHROPSHIRE • Tel.: Well. 1000

LONDON OFFICE: 167 VICTORIA ST. • TELEPHONE: VICTORIA 1000

REINFORCED CONCRETE CONSTRUCTION



HEAVY REINFORCED
CONCRETE RETAINING WALL IN
COURSE OF CONSTRUCTION



**UNITED KINGDOM CONSTRUCTION
& ENGINEERING COMPANY LTD..**

CIVIL ENGINEERING CONTRACTORS
HAMMOND ROAD, KIRKBY INDUSTRIAL ESTATE, LIVERPOOL
TELEPHONE, SIMONSWOOD, 2401 (3 LINES)



*By Appointment to the late King George VI
Manufacturers of Land-Rovers
The Rover Co. Ltd.*


Tough loads . . . rough roads . . .



the **LAND-
ROVER** can take it!
FOUR-WHEEL DRIVE

MADE BY THE ROVER COMPANY LIMITED • SOLIHULL, BIRMINGHAM ALSO DEVONSHIRE HOUSE • LONDON

CV8-83A



1100-ft. Prestressed Concrete Culvert for the Lea Conservancy Catchment Board. Engineer: Marshall Nixon, M.B.E., T.D., B.Sc., A.M.I.C.E., A.M.I.Mech.E

WHICH WAY YOU LIKE . . .




"MACALLOY" BARS FOR USE WITH LEE-McCALL SYSTEM OF PRESTRESSED CONCRETE.

Working Stress of 95,000 p.s.i. An economical and effective system of prestressing concrete, using high-tensile alloy steel in bar form. The steel is provided with positive end-anchorage and does not rely upon bond to transmit the stresses to the concrete.

"MATOBAR" WELDED FABRIC REINFORCEMENT.

To B.S. 1221-1945, Part A. Working Stress of 27,000 p.s.i. Economical for all types of concrete construction. Hard drawn, high-tensile steel wire mesh, electrically welded at every intersection.



"ISTEG" STEEL REINFORCEMENT (MANUFACTURED UNDER LICENCE).

Twin Twisted Bars to B.S. 785-1938 and B.S. 1144-1943. Working Stress of 27,000 p.s.i. Steel bars with a combination of twist and cold working, giving 50% improvement in tensile stress; 30% less weight of steel. Improved bond. Hooks and overlenghts eliminated.

INCREASED WORKING STRESSES.

The stress of 27,000 p.s.i. complies with C.P. 114, but in certain circumstances these stresses may be increased to 30,000 p.s.i. if due care is taken in the design, thereby showing still greater steel economy as recommended in the Ministry of Works Steel Economy Bulletin No. 1.

REINFORCEMENT BY McCALLS

McCALL AND COMPANY (SHEFFIELD) LIMITED

TEMPLEBOROUGH · SHEFFIELD · AND AT LONDON

Tel.: Rotherham 2076 (5 lines)

Tel.: Sloane 0428

SRB 47

GUNITE AND CEMENTATION



Systematic repairs to structures
based on systematic diagnosis of
defects.

WHITLEY MORAN & CO. LTD.

Specialists in the Repair of Engineering Structures

GUNITE

5 OLD HALL STREET, LIVERPOOL.

Telephone: Central 7975



THE "JOHN BULL" CONCRETE BREAKER

NEW "B.A.L." TYPE.

INCREASED:—

PENETRATION, RELIABILITY, LIFE.

REDUCED:—

VIBRATION, NOISE AND WEAR.

THESE ARE THE SALIENT FEATURES
OF THE NEW CONCRETE BREAKER




REAVELL & CO., LTD.
RANELAGH WORKS, IPSWICH.

TELEGRAMS: "REAVELL, IPSWICH."

TELEPHONE: 2124

RUSH & TOMPKINS LTD



WATER TOWER, SHROPSHIRE

RUSH & TOMPKINS LTD.

Building & Civil Engineering Contractors

SIDCUP - LONDON - DURBAN - COLOMBO

★ CHASTON

**SPECIALIST CONTRACTORS
FOR REINFORCED CONCRETE
AND PRECAST PRODUCTS**

WE INVITE YOUR
ENQUIRIES FOR CON-
CRETE WORK OF ALL
KINDS, IN STANDARD
OR SPECIAL DESIGNS

PRESTRESSED STRUCTURAL UNITS

DAVID CHASTON LTD., ESSEX ROAD, HODDESDON, HERTS.
Telephone: Hoddesdon 2264 (3 lines).



**PIN YOUR FAITH
TO THE TESTED
BRAND.**

THIS LABEL ON
EVERY BARREL
CARRIES WITH IT
FORTY YEARS'
EXPERIENCE OF
MANUFACTURE.

**NONE OTHER IS
"JUST AS GOOD"**

THE LEEDS OIL & GREASE CO.


Phone 22480

LEEDS, 10

'Grams: "Grease,"



Then...



...and Now

STOCKTON AND DARLINGTON LINE

Reconstruction of Bridge over the Railway,
Borough of Stockton-on-Tees. Engineer:
C. Cowan, Esq., A.M.I.C.E., M.I.Mun.E.,
A.R.I.C.S.

ONE of the oldest Railway Bridges in the world,
completely reconstructed by Tarslag.


Just one example of the scope of our activities
in the Civil Engineering Field.

TARSLAG

LIMITED

BUILDING AND CIVIL ENGINEERING CONTRACTORS

WOLVERHAMPTON, ROTHERHAM AND STOCKTON-ON-TEES



This time tomorrow

*concrete sufficiently hard
for almost any purpose*

Concrete made with '417 Cement' is ready—for almost any duty—24 hours later. The time saved by its use means important savings in cost and greater productivity of plant, shuttering, etc. Please write for full particulars of '417 Cement.'



'417' cement



QUICK SETTING—EXTRA RAPID HARDENING

THE CEMENT MARKETING COMPANY LTD

PORTLAND HOUSE, TOTHILL STREET, LONDON, SW1

G. & T. EARLE LTD., CEMENT MANUFACTURERS, HULL

THE SOUTH WALES PORTLAND CEMENT & LIME CO., LTD., PENARTH, GLAM.

BRITISH CEMENT IS THE CHEAPEST IN THE WORLD



• • • • •

*

Designed by
Indented Bar & Concrete
Engineering Co., Ltd.

General Contractors :
Costain John Brown Ltd.

• • • • •



Much can be done with Expanded Metal. Here, by way of example, are pictures of the Windshield Wall for the 4½ million gallon settling tank* constructed at the Palliser Works, Hartlepool, for British Periclase Co., Ltd., for which "Ribmet" was used.

More than sixty years' experience suggest that Expanded Metal will prove equally satisfactory for work now engaging your attention.

Expanded Metal

THE EXPANDED METAL COMPANY LTD.

Burwood House, Caxton Street, London, S.W.1. Tel. ABBey 3933
 Stranton Works, West Hartlepool. Tel. Hartlepool 2194

'EXPAMET' PRODUCTS
 Expamet Expanded
 Steel and Aluminium
 Flattened Expamet
 BB Lathing
 Exmet - Ribmet
 Super-Ribmet
 XPM Welded Fabric

Also at: ABERDEEN • BELFAST • BIRMINGHAM • CAMBRIDGE
 CARDIFF • EXETER • GLASGOW • LEEDS • MANCHESTER






Coated Macadam
Concrete Aggregates
Granite Chippings
Crushed & Screened
Rubble

**The ROWLEY REGIS
GRANITE QUARRIES LTD.**
117, Dunstall Road, Wolverhampton

"CAPCO" H. F. VIBRATOR



for compacting mortar cubes
for Compression Test B.S.
12/1947, B.S. 915/1947,
B.S. 146/1947, B.S. 1370/
1947. New type automa-
tic control—optional. The
vibrator illustrated in the
B.S. was built in our works.

The "CAPCO" range of con-
crete testing apparatus also
includes Cube Moulds; Slump
Cones; Tensile, Vicat, and Cylin-
drical Moulds; Tile Abrasion
Machines; Compacting Factor
Apparatus.

Full details on request.

CAPCO (SALES), LTD.

BEACONSFIELD ROAD, LONDON, N.W.10.

Telephone: WILLESDEN 0067-8.

Cables: CAPLINKO, LONDON

(Sole Agents for all
"Capco" Products)



Aerial photograph of British Electricity Authority's Lincoln Power Station.

Consulting Civil Engrs: L. G. Mouchel & Partners Ltd. Contractors: Wm. Moss & Sons Ltd. Concrete Piling Ltd. The Franki Compressed Pile Co. Ltd.

The use of Ciment Fondu in Power Stations

One of the many power stations in this country where Ciment Fondu has been used because of its resistance to mineral sulphates and/or sulphur fumes or weak acids is the Lincoln Power Station shown above.

Ciment Fondu was specified for all concrete work underground because of the peat acid in the soil.

All piles were made with Ciment Fondu and all concrete work to ground level for cooling towers, pond bottoms, pond walls, main building, switch houses, intake house, pump house, ash hoppers, wagon tipper, etc.

Please write for literature.

Concrete Rock-Hard within one day




LAFARGE ALUMINOUS CEMENT CO. LTD.
73 BROOK STREET, LONDON, W.1. Tel: MAYfair 8546

*Dow-Mac
Products
choose—*

**WIRE MANUFACTURED BY
BRITISH ROPES LIMITED for
PRESTRESSED CONCRETE**

British Ropes Limited were among the first producers of wire for prestressed concrete work. Our wire has been used in many important constructional undertakings, both at home and overseas.



Dow-Mac Products Ltd. used our wire in the production of prestressed concrete sheet piles for a curtain wall on the new iron ore quay at Tyne Dock, here seen in the course of erection. The piles were designed by R. B. Porter, Esq. (Chief Engineer, Tyne Improvement Commission) and Messrs. Rendel, Palmer & Tritton, Consulting Engineers.

DONCASTER

**BRITISH
ROPES LTD**


Look for the name **ALLAM**
and buy the best
VIBRATING EQUIPMENT
made today

**FLEXIBLE DRIVE
INTERNAL
VIBRATOR**



The most comprehensive range of Allam internal vibrators includes petrol, electric and pneumatic types with frequencies up to 11,500 r.p.m., and all offered with three sizes of interchangeable vibrating units to suit very harsh dry concrete mixes, various cross-sections, and spacing of reinforcement.

External vibrators are offered in five sizes to suit the weight and shape of the structure to be concreted. They are used as complementary to internal vibrators, or where the section and reinforcement exclude the entry of internal vibrators.



**TRILLOR
ELECTRIC
EXTERNAL
VIBRATOR**

Details of these and other items of contractors' plant sent on request.

E. P. ALLAM & CO. LTD.

LONDON: 45 Great Peter Street, S.W.1.

Telephone: Abbey 6353 (5 lines)

SCOTLAND: 33 Cavendish St., Glasgow, C.5. Tel.: South 0186.

Works: Southend-on-Sea. Tel.: Eastwood 55243



STENT

PRECAST CONCRETE

Piles

PRESTRESSED PILES

STENT PRESTRESSED PILES have satisfactorily withstood practical tests and have the advantages of smaller scantlings, greater length and easier handling. Illustration shows a 12" x 12" x 65 long pile on a site where several hundreds were used most successfully.

STANDARD REINFORCED PILES

STENT G.I. PILES maintain their long proven popularity. They are Reliable, Economic and Ready Available. In shorter lengths, they will probably remain unchallenged even by the STENT PRESTRESSED PILE. Stock sizes: 12" x 12" in lengths 15 ft.-40 ft. 14" x 14" in lengths 15 ft.-55 ft.

AVAILABLE FOR IMMEDIATE DELIVERY

STENT

PRECAST CONCRETE LIMITED

1 Victoria Street, London, S.W.1. Phone : Abbey 2573 & 2416
Works : Dagenham Dock, Essex. Phone : Rainham (Essex) 780

Specify
STENT
For the
RIGHT Pile

L.3835 H

**WATERTIGHT
LININGS
FOR
RESERVOIRS,
SWIMMING
BATHS, ETC.**



**LININGS
FOR
TUNNELS,
SEWERS,
TANKS.**

*Specialists in the Repair and Reconditioning of
Defective Reinforced Concrete Structures, etc.*

THE

GUNITE

CONSTRUCTION CO. LTD

WESTERN HOUSE, HITCHIN, HERTS.



*founded
on
FRANKIPILES*

Swan Flour Mills, Hull.

Photograph by courtesy of Messrs. Spillers, Ltd.

Consulting Engineers: Messrs. Oscar Faber & Partners.

FRANKIPILE

(THE FRANKI COMPRESSED PILE CO. LTD.)

**39 Victoria Street,
London, S.W.1**

Telephone: ABBey 6006-9

'Grams: Frankipile Sowest London

And in AUSTRALASIA, BRITISH WEST INDIES AND SOUTH AFRICA



**Look out! - we're being
BRAYDOZED**

BRAY

W.E. BRAY & CO LTD

TELTHAM, ENGLAND. PHONE TELTHAM 8471-2 (4 L.) CABLES: BRAYDOZER, LONDON.

To move most—fastest—
at lowest cost
**BUY DOZERS BY
BRAY**
Completely British
designed and built Earth-
moving Equipment
FOR FOWLER CHAL-
LENGERS, FORDSONS,
& COUNTY TRACTORS
Write for details of the
BRAYDOZER to suit your
needs.

“CONSTRUCTION WITH MOVING FORMS”

By L. E. HUNTER, M.Sc., A.M.Inst.C.E.

72 pages. 53 illustrations.

Price 7s. 6d. By post 8s. 1.75 dollars in Canada and U.S.A.


Describes and illustrates practical methods of rapid construction with continuously-moving, or sliding, forms. This book will be of assistance to those familiar with the process, and will prevent mistakes being made by those using moving forms for the first time.

PRINCIPAL CONTENTS

- Construction of wooden and steel forms, yokes, and jacks.
- Details of deck, scaffolds, dragging at corners, circular and polygonal bins, and lateral bracing.
- Procedure of construction: Preliminaries. Levelling. Roof. Dismantling.
- Materials. Plant. Reinforcement. Construction in cold weather. Emergency equipment. Labour.
- Reinforcement: Design. Stacking. Cover. Bar schedules.
- Special applications: Structures of variable shape. Structures with floors. Structures without columns. Openings in walls. Tanks. Chimneys. Cost.
- Shutters Travelling Horizontally: For sea walls, culverts, and sewers.
- Hints and Reminders.

CONCRETE PUBLICATIONS LIMITED

14 Dartmouth Street, London, S.W.1, England



Design Engineers: The British Reinforced Concrete Engineering Company Limited.

Rothies Colliery

This contract for the National Coal Board (Scottish Division) East Fife Area comprises the construction, in reinforced concrete, of two Koepe Winding Towers, each 191 ft. high, together with the Car Halls 64 ft. wide by 43 ft. average height. The roof will be of shell construction and the overall length of the buildings will exceed 930 ft.

NOW, AS IN THE PAST...
CUBITTS
BUILD FOR THE FUTURE

LONDON · LIVERPOOL · SCOTLAND · NEWCASTLE · OVERSEAS

HOLLAND & HANNEN AND CUBITTS LTD, ONE QUEEN ANNE'S GATE WESTMINSTER SW1

C95



A symbol of quality materials, experienced workmanship, expert supervision, and excellent service.


for all forms of **PRECAST CONCRETE**

We specialise in the production of Precast Concrete structural members to standard or special designs, also products for the Electrical Industry, Sports Ground Contractors, and Fencing Contractors, and shall be pleased to submit quotations for your requirements.

H.B. CONCRETE CO. LTD.

Head Office and Works: VICARAGE ROAD, EGHAM, SURREY. Telephone: Egham 3092

RAPIER TRUCK MIXERS



and Batching Plants for
scientific and economical mixing
and placing of concrete.



Also makers of a full range of tilting, and non-tilting mixers and self-priming water pumps.

RANSOMES & RAPIER LIMITED

IPSWICH—WATERSIDE WORKS.

32, VICTORIA ST., LONDON.

STEEL SHEET PILING

A NEW HEAVY DUTY SECTION

FRODINGHAM NO. 4



Cross Sectional Area in SQ. IN.	Weight		Moments of Inertia About X-X		Section Moduli About X-X		Modulus Weight Ratio
	Of Section in sq. ft. per foot run	Of Piling in Wall per foot run	Of Section in in. ⁴	Of Piling in Wall in in. ⁴	Of Section in in. ³	Of Piling in Wall in in. ³	
13.84	53.79	40.96	708.67	235.18	57.43	43.75	1.07

Figures in italics are for a single pile and not for the double pile as shown on the diagram.

The new
Frodingham No. 4
section—a heavy duty
piling with outstanding characteristics—
does not show any reduction in thickness of
metal in or adjacent to the locks. It covers
a maximum of area for a minimum weight
per square foot with no loss of strength.
Reference to the modulus—weight ratios
shows the economical efficiency of Froding-
ham sections.

Compare the above properties and remember

FRODINGHAM  FOR STRENGTH

Easy to drive - Easy to Extract - Economical

Full details of Frodingham Piling will be sent on request

APPLEBY-FRODINGHAM STEEL COMPANY

Branch of the United Steel Companies Limited

Telephone:
Scunthorpe 3411 (3 lines)

SCUNTHORPE, Lincs.

Telegrams:
"Appfrod" Scunthorpe

95 FH 66

Sealocure

*cures
concrete*

CONVENIENTLY

Without the trouble of damping down—no wet sacks or sawdust necessary.

SCIENTIFICALLY

Sealocure forms a film over the surface of the concrete, thereby retaining water essential to secure complete hydration.

EFFECTIVELY

Considerably increases tensile and crushing strengths. Test figures substantiated by eminent Consultants.

SIMPLY

Applied soon after the concrete has been placed. No further attention necessary, the Sealocure film disappearing when hydration complete.

On Air Ministry Approved List, and being used by Leading Civil Engineering Contractors.

Sealocure

CONCRETE CURING LIQUID

SEALOCURE PRODUCTS LTD.



ATLANTIC WORKS, HYTHE
ROAD, LONDON, N.W.10
Tel.: LADbroke 0015 6 7.
"Grams": "Exploiture, Wesphone,
London."

Why waste time hacking for a plaster key? — USE

"CONTRASET" CEMENT RETARDER

for either steel or wood shuttering. Write for particulars and prices.


"CONSET" NO. 4

for concrete construction and floors
**THE FOUR-IN-ONE TREATMENT
HARDENER**

**DUST-PROOFER
OIL-PROOFER
ACCELERATOR.**

ALLIED BUILDING COMMODITIES LITTLE ROYD HUDDERSFIELD

Telephone: Huddersfield 2901



Trent Gravels 10,000 tons per week Washed & Crushed 1½ in. to ¾ in.

We are the leading suppliers of high-class concrete aggregates in the area shown above. Prompt deliveries guaranteed and keen competitive prices quoted. Send for samples and prices.

TRENT GRAVELS LTD

ATTENBOROUGH NOTTS
Telephone: Beeston 54255.

"CONCRETE SERIES" BOOKS ON CONCRETE

For a complete catalogue giving prices in sterling and dollars, send a postcard to:
CONCRETE PUBLICATIONS, Ltd.
14 Dartmouth St., London, S.W.1

"RAPID" HAMMERS

**are being used for
fixing door and
window frames by**

Messrs. Wates, Ltd., for the four six-storey
blocks of reinforced concrete flats now
being erected at Wandsworth, illustrated
below.



The top illustration shows a "Rapid" Hammer piercing a window frame and driving a stud into the concrete in one operation, thereby eliminating the costly labour involved in using wooden plugs, and avoiding the difficulty of aligning the plugs with holes in the frame. It is easy to use, and is the most notable labour-saving development yet produced in providing fixing devices to concrete walls and floors for all purposes. For full details, send to :

ADAM & HARVEY (RAPID HAMMER) LTD.

GREENWICH HOUSE, 10/13 NEWGATE STREET, LONDON, E.C.1. Telephone: CITY 6671.

COLLOIDAL CONCRETE MIXERS


These machines make a water-cement-sand grout by high-speed mixing and pump it to the work through a rubber hose. The grout contains no chemical admixtures and is stable and fluent.

When the grout is poured on to the dry aggregate or to the bottom of inundated aggregate it completely fills the voids and makes a dense impervious concrete.

Compared with traditional concreting this method saves about 25% of cement and sand and reduces labour by requiring only 40% of the materials to be handled through the mixer.

for

- MASS WORK
- DAMS
- FOUNDATIONS
- FLAT WORK
- ROADS & AIRFIELDS
- FLOORS
- UNDERWATER WORK
- SEA DEFENCES
- DOCKS & HARBOURS
- GROUTING CABLE CHANNELS OF PRESTRESSED CONCRETE
- METALLIC CONCRETE
- CELLULAR CONCRETE
- ABNORMAL CONCRETING JOBS



COLCRETE LIMITED

GUN LANE • STROOD • KENT • Phone: Strood 7334 & 7736

SHIPPING TERMINAL AT OLD HARBOUR, JAMAICA



Jetty. Transit Shed
under construction for
Alumina Jamaica Ltd.
in connection with
Bauxite and Alumina
Development

Consultants :
Aluminium Laboratories Ltd.,
Montreal

Designing Engineers :
Frederick Snare Corporation,
New York

Construction by

**MARPLES,
RIDGWAY & PARTNERS**
LIMITED

CIVIL ENGINEERING CONTRACTORS

**2, LYGON PLACE, GROSVENOR GARDENS,
LONDON, S.W.1**

Telephone :
SLOane 0781.

Telegrams :
Maripar, Sowest, London

Contractors for :

POWER STATIONS
DOCK AND HARBOUR
WORKS
REINFORCED CONCRETE
WORKS
TUNNELLING IN FREE AND
COMPRESSED AIR
EARTHWORKS
RAILWAYS
MAIN DRAINAGE
ROADS
INDUSTRIAL BUILDINGS,
ETC.

KOPEX TUBES

for

PRESTRESSED CONCRETE

the new and
better method of
forming **CABLE DUCTS**

WILL BEND TO ANY SHAPE AND REMAIN RIGID

The use of KOPEX TUBES by Engineers and Contractors has already proved that they afford a simple means of forming cable ducts with unskilled labour and without fixing equipment for the most intricate prestressed concrete design. This new development in prestressed concrete work should be investigated by all Engineers and Contractors engaged in this class of work, to whom we will be pleased to submit samples and full details.

UNI-TUBES LTD.

9 SOUTH MOLTON STREET, LONDON, W.1.
Telephone: MAYFAIR 7015.

WORKS: ALPHA STREET, SLOUGH.
Telephone: SLOUGH 24606.

JULES WEITZ TOWER CRANE



**will always reduce
handling costs in
construction work**

The illustration above shows a Jules Weitz Type 15/20 Mono-Tower Crane in use by Messrs. Wates, Ltd., for the construction of six-story blocks of flats in reinforced concrete at King's Avenue, Clapham, S.W.4.

Jules Weitz Tower Cranes, of which the various types range from 12 cwt. to 20 tons capacity, are designed for fast lifting and accurate spot placing and are in use on important construction works in all parts of the world.

The "Type 15/20" Crane has a capacity of 15 cwt. at maximum 65' 6" radius, and 3 tons at 20' 0" radius; lifting height 75' 9" jib horizontal—133' 0" jib raised. Speed of lift 150' 0" per minute.

A JULES WEITZ PRODUCT

Full particulars from the Sole British Distributors.

MACHINERY (CONTINENTAL) LTD

175 BROMPTON ROAD, LONDON, S.W.3

TELEPHONE: KENSINGTON 6228

When the Designer consults the Mould Maker

Before the Engineer completes a design incorporating precast structural members he can be certain that his intentions will be executed by the soundest and most economical methods if he has the advice of an experienced mould maker. Ease of stripping; accuracy; regularity of quality of concrete unit; constant use of moulds; maximum interchangeability of moulds; minimum expenditure of labour: these factors vitally affect final cost. We specialise in the design of moulds for all types of precast structural members, and are always at the service of Designers who wish to ensure that their designs can be properly and economically carried out.



BETHWIN ROAD

LONDON, S.E.5

Telephone : Rodney 5981

CONCRETE AND CONSTRUCTIONAL ENGINEERING

INCLUDING PRESTRESSED CONCRETE

Volume XLVIII, No. 9.

LONDON, SEPTEMBER, 1953.

EDITORIAL NOTES

A Book by M. Le Corbusier.

THE ideas of the French architect M. Le Corbusier have invariably aroused enthusiastic praise or hearty condemnation. The Unité d'Habitation de Marseille is no exception. This immense structure (which is illustrated on pages 300 and 301) contains 337 flats, shops, an hotel of eighteen rooms, a nursery, and a kindergarten, and there are a swimming pool and a gymnasium on the roof. The building is 450 ft. long by 80 ft. wide by 180 ft. high, and has accommodation for 1,500 people. It is supported at about 25 ft. above the ground by reinforced concrete piers which carry the seventeen stories. Along the middle of every other story is a corridor, called a street, served by lifts. The entire building is of reinforced concrete. This structure is briefly described in a recently published book,* from which our illustrations are taken. Architects will be profoundly interested in the planning of the flats and of the building as a complete community, but there is little of interest to the structural engineer; it is indeed a pity that so much of the book is devoted to controversy with those who have criticised the author's ideas on how people should live and so little to technical details of the construction.

In the design of this great structure there are two predominating ideas. The first is that people should live in immense blocks of flats built in the open country, with facilities for shopping and sport within, on top, or under the building, and be able to enjoy the countryside; this idea has not, so far as we know, been strongly advocated in the past. The second idea to which great importance is attached is one that has probably been striven for from the days when man first started house-keeping, and that is that the home should be designed and furnished for the greatest convenience and pleasure of the occupants, although ideas of what are conveniences and pleasurable have changed through the centuries. The author has extreme ideas on what is convenient. He likens a home to a bottle, and says that homes, like bottles, should be stored in bins. All bottles containing the same kind of wine are of the same shape, so the author's view is that all homes should be exactly alike. The savings due to the mass production of identical fittings and furnishings must be taken advantage of to the utmost. The structure is also called a box of homes, and the homes are said to be pigeon-holed in this box as shown in the illustration on page 300.

These ideas have naturally been criticised by people who prefer the garden city type of development in which each house has its own garden, as is mostly

* "The Marseilles Block." By Le Corbusier. Translated by Geoffrey Samsbury. (London: The Harvill Press, Price 21s.)

the case with the new towns and estates on the outskirts of cities in Great Britain. The separate house is described by M. Le Corbusier as a mausoleum, and criticism of the bottle-and-bin idea is called the venomous outpourings of poisonous little scribes. The author describes how he was permitted to build free of all building regulations. The Minister of Reconstruction is quoted as telling him that in this work he would be above the law; that the architect could innovate to his heart's content and would alone be responsible for the results. He is indeed a remarkable man who can persuade a government to place his building activities above the law, and who so fiercely replies to critics.

Another unusual attribute of M. Le Corbusier seems to be an idea that his work is specially favoured by nature. For example, now that the building is in being he claims that nature has responded to his efforts and laid her hand upon his work. A lesser man might have been content to claim that he had not spoilt the countryside or, at most, in the jargon of the day, that the building harmonised with its surroundings. Over a long period of years the elements will change the hue and texture of most building materials, and often mellow and improve their appearance, but never before have we heard an architect claim that nature has blessed a new building. It is also stated that a "unit of appropriate size" will bring nature down to the human scale, whereas most people would think that the unit of size adopted by an architect affected the scale of the building rather than reduced the size of nature. We are further told that the module adopted has kept the building comely, smiling, graceful and human. There is no doubt that the comeliness of a building is determined by its scale and proportions, but to people with less imagination it may seem preposterous to claim that an inanimate material has human attributes; it is common to be asked by architectural pundits to believe such an impossibility as a building material expressing itself, but to ask us to imagine that a block of flats is smiling at us is setting a task which we find as difficult as seeing a meaning in pieces of bent wire that are called sculpture. If we may risk being classed with the outpourers of venom, we would say that it is as ridiculous as it is unnecessary to claim that nature has blessed this or any other building, and that we have yet to see a block of flats break into a smile. We are reminded of a sentence in Mazzini's essay on Carlyle: "Genius is . . . the conscious power of the soul of a man rising from amidst his fellow men, believing and calling himself a son of God, an apostle of eternal truth and beauty upon the earth, the privileged worshipper of an ideal as yet concealed from the majority."

M. Le Corbusier is a great architect of international repute who has contributed new ideas to his art. He has been awarded the gold medal of the Royal Institute of British Architects. He has now had the opportunity of embodying in a unique structure his ideas of what is the best way of living. He has produced a fine building, a clever plan, and labour-saving homes for those who like the idea of spending their home life in one of 337 pigeon-holes. But those who think it better that a family should have a separate home on its own plot of ground, and who think that a home should be something more than what the author of this book has called "a machine to live in," are entitled to air their views, and will probably continue to do so, howbeit with less abuse than M. Le Corbusier heaps upon them. It is disappointing to the reader that so much of the book is devoted to a recital of squabbles between the author and those who have disagreed with him.

The Application of Reinforced Concrete to School Buildings—1.

With particular reference to Precast and Prestressed Concrete.

By FELIX J. SAMUELY, B.Sc., A.M.I.C.E.

THERE are certain problems common to a great number of school buildings, although they often vary in detail with the design. During the past few years, on account of various shortages, precast, and especially prestressed, units have been particularly useful, and there is no doubt that even if there were no shortages such constructions would still be of great use. The following is based on experience gained by the writer in the design of the structure of a number of schools, a list of which is given at the end of this article. The most important components of schools are classrooms, dining halls, assembly halls, gymnasias, and workshops, each of which presents special problems.

General Principles of Construction.

In order to get definite experience of certain problems it is necessary to consider alternative methods, but if too many variations were considered at the same time it would be difficult to analyse the problems. However, in all the schools of which the structures were designed by the writer certain principles of construction were kept the same and an analysis is therefore possible. The principles on which all these schools were designed are as follows.

(a) Precast concrete was introduced to a varying degree, but in every instance it was done in such a way that the erection of precast concrete would be carried out without reference to the in-situ concrete work. In other words, all the precast units are either mechanically connected by steelwork or are stable due to their own weight alone. In no case was grouting or in-situ concrete an essential part of the erection of a precast unit.

(b) Nevertheless precast concrete units were invariably used in such a way that general rigidity of the building was obtained by an in-situ topping. The combination of precast concrete with an in-situ topping is sometimes called "composite construction" * and has many advantages. In order to comply with (a) the in-situ concrete was arranged in every case so that it was not part of the general erection scheme.

(c) As precast concrete depends very much for its economy on repetition, parts where repetition did not occur, for example entrance halls, special corners, gable walls, etc., were usually built in-situ. In some instances all repetitive slabs, beams, and columns were precast; in other cases the columns were cast in-situ and only the beams and slabs were precast. Special attention was given to the problem of not mixing precast and in-situ concrete too much; for example, if a non-standard beam had to be cast in-situ and supported by a standard column, the column was constructed in-situ even if all the other identical columns were precast. The reason is that the combination of a precast column with an in-situ beam makes erection extremely difficult. It is the writer's belief, and is borne out by his experience, that the future of precast units depends on a sensible consideration of the method of erection, and that the indiscriminate use of precast and in-situ concrete together can easily lead to uneconomical construction.

* See the writer's lecture to the Institution of Civil Engineers, February 5, 1952.

(d) The lowest unit cost of a precast member is obtained when not fewer than 50 to 100 are made, and beyond this number there is no reduction in cost. The saving is due to the repeated use of the moulds, but it is not very costly to have small variations in units which do not require an increased number of moulds because such variations can be obtained by inserting liners, blocking-pieces, tubes, etc., in a standard mould. For most small units, for example floor slabs and short beams, sufficient repetition can be found in one school, so that there is no need for a standard grid throughout the country. It has even been possible to have, without adding to the cost, two or three grids in the same building and yet have sufficient repetition to make precasting economical. The grids used in these schools, which in every case have been suggested by the architect to meet the requirements of the plan, are 3 ft. 4½ in., 4 ft., 5 ft. 6 in., 6 ft., 6 ft. 8 in., 6 ft. 9 in., 7 ft. 4 in., 7 ft. 6 in., 8 ft., 8 ft. 3 in., 10 ft., 12 ft., and 15 ft.

A greater difficulty arises with main beams because there are far fewer of them, and in a small school it would be difficult to use the minimum number of the same units which would ensure real economy. For general guidance, a school costing about £50,000 would allow one type of main beam to be precast economically, while larger schools would allow of several types. However, special problems arise, even in small schools, when a variety of main beams is required, for example, one for the roof and one for the floor construction. It may also be that classrooms in the same school have not a constant width, while dining halls and possibly gymnasias and assembly halls also present special problems. It was found desirable, therefore, to apply a certain amount of general standardisation to the main beams, and one of the main difficulties was to find standard units which could be used in various cases; these are referred to later under "Prestressed Planks".

(e) There should be no difficulty in lifting heavy precast units for school construction. There is, however, the question of transport to the site. It has been found generally that units up to 40 ft. long can be made in a factory and taken to the site. In the case of prestressed concrete it is the writer's experience that the bonded method is best. However, it has occurred several times that at small extra cost post-tensioned units could be obtained much quicker because they do not depend on prestressing beds being available. In the case of units longer than 40 ft., or of frames with an awkward shape, it is usually better to precast them at the site. In the case of prestressed units it is sometimes possible to precast short parts and post-tension them at the site. In one case only did the question arise of post-tensioning in-situ concrete (see reference to the assembly hall floor at Hatfield School).

Classrooms, Administration Rooms, Drawing Rooms, etc.

DEPTH OF FLOOR.—These rooms usually require a structural frame for wings of lengths varying from about 30 ft. to several hundred feet. The width of classrooms varies from 20 ft. to 27 ft. In the case of a classroom it may not always be possible to satisfy all the requirements. The standard construction consists of a number of cross-beams on grid lines with a slab spanning parallel to the front of the classroom. In the writer's experience, however, these cross-beams often present great difficulties because (a) they interfere with the arrange-


ment of any partition walls, particularly when the beams are latticed, (b) the flexibility is restricted (which is important because of the possibility of changing the plan of the school at a later date), and (c) very frequently the floor-to-floor height of classrooms has to be increased because of the use of deep beams; it has been stated that the apparent necessity of such latticed beams was the reason for the very high classrooms that were at one time requested by the Ministry of Education. While some schools have visible cross-beams, a considerable amount of thought has been given to the problem of avoiding their use altogether and producing a completely flat ceiling which allows the maximum flexibility and gives the greatest amount of headroom.

LIGHTING.—Another important problem is lighting. In order to have good lighting, rooms need a certain height; and the nearer the entry of light is to the ceiling the lower can be the room. For this reason it is better not to have a lintel between the top of the window and the ceiling, and some architects also dislike the shadow created. Sun-blinds are necessary, and apparently no suitable types have been developed which can be pulled up from the sill. The blind, when closed, has to be in a box and this box, if under the ceiling, has the same effect as a lintel. It is therefore desirable to recess the box for the blind in the floor construction. This is simple when the floor spans parallel to the windows and when the beams are not wider than the columns; but if an attempt is made to do away with such beams altogether, or make them shallower but wider than the columns, special difficulties occur.

SLOPING CEILINGS.—Most architects prefer a flat ceiling, but in two cases (Hatfield College and Hatfield Technical School) the requirement was a sloping ceiling which allowed the same amount of light with a much smaller floor-to-ceiling height in the centre of the building and gave an opportunity to use substantial floor trusses and to have the heating installation in the space between the false ceiling and the floor (see Fig. 3, "Concrete and Constructional Engineering," February, 1952). In this case, which incidentally was designed before prestressing was developed so much as it is now, trussed beams are used. The same types of beams are used in the college and in the school, and the number of types was reduced to four. The trussed beam was selected because it was the simplest combination of steel and concrete with no intermediate diagonals, and a flat strip was used for the lower chord because it was easy to bend to the required shape. In the college the columns were precast, but in the school they were cast in-situ. Fig. 1 shows the three connections, namely, two (b) and (c) to the precast columns and one (a) to in-situ columns. In the precast columns the plate projects and a slotted plate on the precast beam was fitted over it and fixed by square wedges. The in-situ columns were cast up to the level of the beam-support and the beam fitted over a threaded bar in the column to which it is held by a nut. While the erection was very simple in both cases, the fitting of the projecting plate into the precast column was a very expensive item, particularly as the plate had to be fitted absolutely accurately.

TRUSSED BEAMS.—Trussed beams have been used in others of the schools. In Torells School (Fig. 2) a trussed beam was used in combination with precast columns with connections similar to those shown in Fig. 1, but in this case the lower chord was left visible. The main difference between these beams and those at Hatfield is that the struts were made of tubes and arranged vertically to suit

the architects' requirements. The position of these struts was very much controlled by the position of the lighting points. The central panel was much longer than at Hatfield, although the overall span was the same; this resulted in a considerably deeper beam over the top chord (10½ in. instead of 7½ in. overall). In both cases only 3 in. of the top chord are part of the precast units, and troughs were used to span from beam to beam, at 5-ft. 6-in. centres at Hatfield and at 7-ft. 6-in. and 10-ft. centres at Torells (Fig. 3). On top and between the troughs



CONNECTION OF TRUSSED BEAM TO COLUMN.

Fig. 1.

in-situ concrete was placed and acts together with the precast work due to stirrups projecting from the precast units. These stirrups also keep the troughs in position, and with this method it was found that 1 in. support for the troughs was sufficient. During the placing of the topping the trussed beams were supported under the struts; no special scaffolding was required for the troughs, and each trough was strong enough to carry the weight of the wet concrete already placed and of a barrow filled with concrete.

PRESTRESSED TRUSSED BEAMS.—When prestressed concrete was further developed the trussed beam lost its attraction for a time. While the great depth that can be achieved with a trussed beam results in a decrease of steel without

increase of concrete and of weight, and in a very light-looking construction, it appeared that prestressing of the lower chord would be difficult due to its cranked shape. Recently the problem has been overcome, and in *Fig. 4* a trussed beam is shown which is used for several of the schools in Kent—in the first instance at a school at Penge Melvin. In this case the lower chord consists of wires which were post-tensioned by two jacks built into the struts. These jacks produce initial tension only at the factory, and the wires are tensioned at the site to carry the full load. As the wires are kept in tension merely by turning a nut,




Fig. 2.




Fig. 3.




Fig. 4.

and as the force in the strut is only about one-sixth of that in the lower chord, it was possible for the tensioning to be done by two unskilled workmen who prestressed a beam in ten minutes. In this case the beam has an upper chord 4 in. by 6 in. spanning 25 ft. and supports wood-wool slabs only. It was important to reduce the weight of the truss because, with the very small dead and live loads of the roof, the weight of the concrete could have become an important item. The trussed beam, however, weighed less than 30 lb. per linear foot for a total load of about 240 lb. per linear foot.

HOLLOW-TILE FLOORS.—In many classrooms it is desirable to have shallow beams or no beams at all, and the problem of achieving a beamless floor economically is worth considerable thought. In spite of prestressed concrete, the writer has found that hollow-tile floors spanning from front to back of the classrooms are economical and were used at the school at Cubitt Town (Fig. 5). With hollow-tile floors with in-situ ends it is feasible even to reduce the thickness at the front and back locally to provide space for a blind-box. This hollow-tile floor had the disadvantage of requiring shuttering and steel, neither of which was readily available at the time. In some schools the writer has used proprietary precast floors, notably at Blackwell Secondary School, Middlesex.

Prestressed Planks.

Due to standardisation, proprietary floors do not lend themselves very easily to such special problems as blind-boxes, etc. The construction then used by the writer on a great number of schools was prestressed beams spaced apart




Fig. 5.

with various methods of filling between them. The principal reason was that prestressed concrete could be used more economically than reinforced concrete in shallow beams. While for ordinary reinforced concrete floor beams a depth-to-span ratio of 1 : 16 to 1 : 20 appears to be economical, for prestressed concrete the ratio is nearer 1 : 25 to 1 : 30.

Applying the foregoing to classrooms, which usually have a span of about 24 ft., it is found that a construction depth of about 12 in. is suitable in prestressed concrete and this thickness is not too large for a floor. In other words, prestressed concrete allows a reduction in the depth of beams so that they do not project below the soffit of the floor, although a false ceiling may be required.




Fig. 6.




Fig. 7.

The soffits only of the beams were prestressed, partly because this was the most economical way of prestressing, and partly because the top concrete is so much cheaper placed in-situ and at the same time provides a monolithic floor; also, it was possible in this way to standardise the depth in three types and to use the same three types in all the schools (and other buildings as well), even though the loads, spacings, and lengths differed considerably. This is made clear by Fig. 6 which shows the same type of plank being used for a beam having a bending moment of 73,500 ft.-lb. and a beam having a bending moment of 270,000 ft.-lb.




Fig. 8.




Fig. 9.




Fig. 10.




Fig. 11.




Fig. 12.

The standard soffit members are shown in *Fig. 7*. The rather odd overall dimension in *Fig. 7* is a result of placing wires in the soffits at definite centres and forming standard holes for fittings.

A special problem that arose with all the schools dealt with in this article was the question of the blind-boxes cutting into the soffits, as the soffits were always wider than the columns. The solution of this problem was easier because the bending moment was naturally very small at the ends of the beams where the blind-boxes occurred and special bars were arranged, projecting from the prestressed unit into the in-situ concrete, to resist shearing forces; *Fig. 8* shows this method at Paragon Road School.

The greatest difficulty to be overcome was the practical one of how to achieve a flat ceiling. The various solutions for these intermediate floors are shown in *Fig. 9*. Structurally, the most satisfactory solution appeared to be floor-troughs in combination with prestressed units. These troughs, of the same type as those mentioned earlier, were used, for example, at Woodberry Down Comprehensive High School and Wigan Technical College, the gymnasium at Eastcote Lane School, and others. In some cases, for example the changing-




Fig. 13.

rooms at Eastcote Lane School, the architects allowed the coffered ceiling produced by the troughs to be visible, and in these cases the construction is quite satisfactory. Where the architect preferred a flat ceiling, however, a false ceiling was required and additional cost occurred. Such a false ceiling can be arranged either under the soffit to give a true flat ceiling as at Woodberry Down (*Fig. 10*), or immediately under the troughs to give the appearance of wide beams as at Old Palace School (*Fig. 11*). As a false ceiling cannot span from beam to beam it usually has to be hung from the points between the troughs, and in *Figs. 10* to *12* various methods are shown which have been used to hang the ceiling.

An entirely different method of providing a flat ceiling (at Cottingham School) is shown in *Fig. 13*. In this case concrete ribs were arranged at 2-ft. centres, forming secondary beams. On top of these beams were placed wood-wool slabs spanning between the ribs and a thin concrete slab was cast on top of the wood-wool. This construction forms a grid of 2 ft. only for a false ceiling, and either plasterboard or building-board can be nailed to the ribs, which have a timber fillet inserted for the purpose. Incidentally, these ribs were found to be satisfactory in prestressed concrete only, because it was very difficult in ordinary precast concrete to produce narrow ribs with a timber fillet without considerable breakages at the fillet on the site.

Again, a different construction (*Fig. 14*) was used at Barley Lane School (Essex) among others. Here a hollow floor was arranged with precast concrete units at the bottom fixed to intermediate ribs. The intermediate ribs are similar to those in *Fig. 13*, but were much simpler to make as they do not contain a timber fillet. This construction could be plastered immediately.

An alternative to this construction for roofs is shown in *Fig. 15*. Here precast slabs form the soffit and wood-wool slabs with a concrete screed form the top. A variation of *Fig. 14* was used at Wigan Secondary Technical School, where the main beams were at 3-ft. 4½-in. centres only, in accordance with the general grid, and therefore it was possible to omit secondary ribs. The lower concrete units were required by the architect to show a special coffering effect (*Fig. 16*), while the upper unit was replaced by corrugated steel covered with in-situ concrete.

Still another construction was used at Paragon Road School, Hackney. In this case the grid was 8 ft. and inverted precast tee-beams were arranged to span this distance, with either wood-wool or corrugated steel sheeting carrying the top in-situ concrete (*Fig. 17*).




Fig. 14.




Fig. 15.




Fig. 16.




Fig. 17.




Fig. 18.—Cross Section through Typical Tee-floor.

Each of these constructions appeared to be practicable. None of them was entirely satisfactory insofar as the cost of the intermediate construction was much too high compared with that of the main beams. A further development to overcome this difficulty has been the use of inverted tee-beams together with an in-situ topping cast on permanent shuttering (*Fig. 18*). This is at present being developed and will be used at a number of schools now being built, but as no experience is available a brief description only is given. Floors of the cross section shown in *Fig. 18* must have a depth of about one-fortieth of the span for normal loads, and can in fact be used for a great variety of spans. Where special loads occur, as for example where cross-walls are to be supported, a stronger floor can be produced by filling the voids with concrete and adding reinforcement near the lower flange. It is generally recommended to form vee-joints between the tee-beams at the bottom and not to plaster them, but alternatively they may have vee-joints at the top which are filled with grout and then plastered on the underside.

SCHOOLS REFERRED TO

Hatfield Technical College and Hatfield Technical School. Messrs. Easton & Robertson, F.R.I.B.A., architects.

Wigan Secondary Technical School and Wigan Technical College. Mr. Howard V. Lobb, C.B.E., F.R.I.B.A., and Mr. Grenfell Baines, F.R.I.B.A., architects.

Cottingham Secondary School. Mr. K. F. Giraud, A.R.I.B.A. (architect of East Riding County Council).

Primary and Infants' School, Old Palace, Poplar. Mr. C. C. Handisyde, A.R.I.B.A., A.A.Dip., architect.

Secondary School, Paragon Road, Hackney. [In conjunction with Mr. F. R. Bullen, B.Sc.(Eng.), M.I.C.E.] Mr. Howard V. Lobb, C.B.E., F.R.I.B.A., architect.

Primary School, Kingsmead, Hackney. Mr. George Fairweather, F.R.I.B.A., architect.

Cubitt Town School. Mr. Howard V. Lobb, C.B.E., F.R.I.B.A., architect.

Roman Catholic School, Tottenham. Messrs. Hiscock & Duncan Scott, architects.

Primary and Infants' School, Valley Hill, Loughton. Messrs. Westwood, Sons & Harrison, architects.

Primary and Secondary School, Barley Lane, Ilford. Messrs. Hiscock & Duncan Scott, architects.

Torells Secondary School, Little Thurrock. Messrs. Westwood, Sons & Harrison, architects.

Primary and Infants' School, Abingdon. Messrs. Bridgwater & Shephard, architects.


Comprehensive High School, Woodberry Down, Stoke Newington. London County Council Architect's Department.

Secondary School, Eastcote Lane, Middlesex. Middlesex County Council Architect's Department.


Blackwell Secondary School, Middlesex. John and Elizabeth Eastwick-Field, architects.

Several Primary Schools for Kent County Council. Kent County Council Architect's Department.

(To be concluded.)



"THE STANDARD CELL."



From "The Marseilles Block."

THE SUPPORTING PIERS.

A Block of Flats near Marseilles. M. Le Corbusier, Architect.

(See p. 287.)



From "The Marseilles Block."

A Block of Flats near Marseilles. M. Le Corbusier, Architect.

(See page 287.)

Book Reviews.

"Prestressed Concrete." By Y. Guyon. (London: "Contractors' Record and Municipal Engineering," 1953. Price £3 10s.)

THIS book of more than 550 pages, first published in Paris in 1951 and now translated into the English language, is confined to the design of simply-supported beams. The text is based on mathematics, frequently of a high order, and includes numerous examples of the work of M. Freyssinet (who contributes a Foreword) and other French engineers. The book also describes a large amount of testing and research work. The various systems of prestressing are described, and methods and materials, with particular reference to the properties of high-tensile steel wire and to the production of concrete with suitable characteristics and of sufficient strength, are discussed. The work is well illustrated and contains numerous diagrams, tables, and references to research, the testing of structures, fire resistance, local stresses in the concrete due to anchorages, and other physical properties. Design is treated in great detail for beams of constant cross section and of variable depth, and the advantages of curved and straight cables are fully discussed and illustrated. Much new matter and information not previously available in book form is included.

The book, while interesting and informative throughout, requires, if it is to be assimilated and appreciated, most careful attention and profound study. It will doubtless be appreciated by many of the younger scientifically-minded engineers who are interested in the subject. The book would not serve as a handbook for quick reference.—R. P. M.

"Concrete Mix Design. A Practical Method for the Production of Quality Concrete from Available Materials." By L. Boyd Mercer. (Melbourne Technical College Press. 1953. Price not stated.)

THE purpose of this book is to present a practical method for producing high-quality concrete. Its principal object is to show how to make the best use of aggregates that may not be well graded, but the method described can be more easily used for suitably-graded aggregates.

The calculations start from the compressive strength used in designing a structure. This strength, when multiplied by a factor of safety, gives a minimum permissible crushing strength. From this a

"target" strength is fixed sufficiently high to ensure that a few only of the test pieces have less than a practical minimum strength. A statistical method for doing this is given. This is followed by a description of the commonly-used methods of relating the crushing strength and the cement content to the water-cement ratio, and calculating the proportion of fine to coarse aggregate that gives a combined aggregate having a grading corresponding as closely as possible to a "base" or type-grading curve. The author gives his own base grading curves and makes a feature of showing how to design gap gradings. Using the calculated proportions, a trial mixture is made and if necessary the proportions are changed and another trial mixture is made.

Short chapters deal with the economics of making concrete; the properties and testing of cement; the quality, grading, and specification of aggregates; the relation of grading to compaction, segregation, and proportions; the variations in proportioning, mixing, and testing concrete; and the application of statistical methods to the proportioning of mixtures. The diagrams necessary for the application of the method are given, together with examples.

The book is obviously based on wide experience of aggregates in different countries and of the application in practice of the methods described. The author's outlook is practical, and is based on a sound knowledge of theory and experiment. The book is a readable and concise introduction to the proportioning of concrete mixtures, as well as a clear exposition of a simple, practical, and easily-applied method of making the best use of aggregates that are economically available.—H. N. W.

"Reactions between Aggregates and Cement." National Building Study No. 15. (H.M. Stationery Office. Price 12s.)

THIS is mainly a résumé of the literature on the alkali content of cements and aggregates. The conclusion is reached that there is no risk of deterioration of concrete, due to alkali reaction, in the case of British aggregates except possibly andesite. This is the second National Building Study on this subject, and it is stated that a third is forthcoming.

A Graphical Method of Designing Cylindrical Shells.

By PROFESSOR A. L. L. BAKER, B.Sc., M.Inst.C.E.

THE advantages of the graphical method described in the following are that it gives a quick solution, helps to avoid errors in computation, and enables the designer to visualise the influence on the bending stresses of the shape of the shell and the distribution of load. Moreover, since the ultimate value and distribution of stress in the concrete cannot be precisely determined, and the strength of the concrete is not generally of critical importance, the method may often be sufficiently accurate for practical purposes.

The following assumptions are made, and are acceptable for conditions prior to failure due to longitudinal bending.

(1) The shell spans longitudinally between supports as a beam of hollow cross section subjected to transverse bending.

(2) Concrete has no tensile strength and is assumed to be cracked below the neutral axis in considering the main longitudinal bending stresses, tensile forces being resisted by the main reinforcement at the edges. In some cases advantage may be taken of the resistance to tensile forces of the longitudinal reinforcement between the edges and the neutral axis.

(3) The main longitudinal compressive stresses due to bending are uniformly distributed above the neutral axis along the arc of the cross section (*Fig. 1c*). A condition approximating to this occurs before failure can take place by crushing of the concrete.

(4) The longitudinal strain due to longitudinal bending as a hollow beam is proportional to the vertical distance from the neutral axis.

(5) Longitudinal bending stresses in the slab are negligible. This is a safe assumption, and is true when strips of the shell spanning longitudinally are sufficiently flexible relative to strips spanning transversely, due either to their length or to cracking caused by longitudinal bending of the whole shell as a beam.

(6) Torsional resistance of the slab may be ignored. This is a safe assumption and may be necessary since torsional resistance is reduced by cracking.

Considering the shell as a beam of partly cylindrical or polygonal cross section, when calculating the longitudinal bending stresses the position of the neutral axis can be determined in the usual way for reinforced concrete beams from the assumed distributions of stress and strain, and suitable values of E for concrete and steel, by satisfying the conditions that (i) Total compression must equal total tension and (ii) Strain is proportional to the vertical distance from the neutral axis.

The distribution of longitudinal bending stresses determines the distribution of shear in the plane of the slab (sometimes called the "membrane shear") along the edges of a strip such as a, b, c, d (*Fig. 1c*). If the tension is concentrated at the edge and the compressive stress is uniform along the arc, then the distribution of membrane shear along the arc will be as shown at (*b*), that is a rectangular distribution below the neutral axis and a triangular distribution above the neutral axis (for a triangular distribution of stress above and below the neutral axis the distribution of membrane shear would be parabolic, and for uncracked sections below the neutral axis such a distribution might be assumed).

The distribution of the difference of membrane shear between two sections such as a-c and b-d (*Fig. 1c*) is the same as the distribution of shear at either section, so that a strip such as a, b, c, d in a symmetrical shell symmetrically loaded is kept in equilibrium by forces as shown at (*a*), namely, downward loads P_1 to P_4 on segments such as A-B, B-C, etc., differences of shear across the strip such as S_1 , S_2 assumed to act tangentially at the centre of each segment A-B, B-C, etc., and whose value is proportional to the width of the shear-distribution diagram in *Fig. 1b* at appropriate points along the arc. The longitudinal bending




Fig. 1.

stresses acting on the strip do not affect equilibrium or bending in a transverse plane, and may be ignored for this purpose. The only remaining force is a tangential thrust R at the crown from the other half of the cross section. The assumptions in regard to the distribution of longitudinal bending stresses enable the distribution of the difference of shear on each transverse strip such as a, b, c, d to be directly determined, and so a statically-determinate method is provided. The external forces [shown in section at (*a*)], maintaining in equilibrium in the transverse plane a strip such as a, b, c, d (*Fig. 1c*), isolated by cuts from the rest of the shell, may be determined vectorially.

In *Fig. 1a* vectors 1-2, 2-3, 3-4, and 4-5 are drawn parallel to tangents at the mid-points of segments A-B, B-C, C-D, and D-E, and in length are propor-

tional to the appropriate widths of the shear diagram at (b). Vectors 5-6 and 1-6 are drawn parallel to the thrust R and the loads respectively. Vector 1-6 is divided into lengths proportional to the loads, so that 6-7 is the vector for P_4 , 7-8 for P_3 , and so on. Now vector 1-6 represents the total load on the strip a, b, c, d which may, for convenience, be of unit width. The scale of the polygon of forces is thus determined. If imaginary cuts are made at B, C, and D, and the internal forces thus removed are replaced by equal and opposite external forces, the forces keeping the segments A-B, B-C, etc., in equilibrium in a transverse plane may be determined. At each cut it is necessary to apply equal and opposite radial shear forces and circumferential thrusts acting on the segments on each side of the cut. Force polygons may be drawn for each segment. Starting with segment D-E, vectors 7-10 and 4-10 are drawn parallel to C-D and a radius through D respectively. Vectors 7-10 and 4-10 then represent to scale the thrust and radial shear from segment C-D acting on segment D-E. Vectors 8-11 and 11-3 are drawn parallel to B-C and a radius through C and represent thrust and radial shear forces from segment B-C acting on segment C-D. The polygon of forces for segment C-D is therefore 7-8-11-3-4-10. Similarly, 8-9-12-2-3-11 is the polygon of forces for B-C, and 9-1-2-12 the polygon of forces for A-B, 9-12 being parallel to A-B and 2-12 parallel to a radius through B. The force R is resolved into radial and horizontal components represented by vectors 5-13 and 13-6, the latter being the value of the radial shear in segment D-E between the mid-point and the crown. The circumferential thrusts and radial shears in the transverse strip can now be scaled from the force diagram. The latter may be plotted on the straightened arc as shown at (e) ignoring the radial components of the thrusts and assuming the shear to be normal between the mid-points and equal in value to the radial shear between the segments. The transverse bending moment in the transverse strip at any section is equal to the area of the shear diagram to the left of the section. The maximum bending moment is at E and is equal to the area of the whole diagram.

The distribution of shear, transverse bending, and transverse thrust may be investigated in this way at any cross section. Close to the supports the concrete may be uncracked, but the same procedure can be followed except that the shear distribution below the neutral axis is assumed to be parabolic. A small number of segments has been used for clarity; greater accuracy is obviously obtained if the transverse strip is divided into a greater number of segments, but such accuracy is not so important as investigating possible positions of the neutral axis and distributions of load for extreme conditions. Values of transverse bending-moments are sensitive to changes of membrane shear distribution. It is therefore more important to consider variations of this influence than to be fastidiously accurate in calculating the bending and shear stresses from values which are themselves only approximate.

The method can be applied to any shape of cylindrical or prismatic shell in which the distribution of longitudinal bending stresses, after cracking and prior to failure, approximates to that of a beam of hollow section. An edge-beam when cracked may be considered as part of the section of the shell. The vertical upward shearing forces at the edge may produce near the edge transverse "radial" shearing forces of opposite sign to those over the inner part of the shell, thus producing a reversal of bending moment. A similar condition may occur when

the load is concentrated close to the crown. Since the value of the downward transverse bending moments due to the load depends only on the value and position of the loads, when the bending moments due to load are greater than the upward bending moments due to shear the resultant transverse bending moments will be greatest when the bending moments due to shear are lowest, that is when the neutral axis is at the highest possible position so that the difference of shear stresses is a minimum.

Cantilevered Shuttering for Bridges.



IN our August number a prestressed bridge at Worms, Germany, the spans of which were built with the aid of cantilevered shuttering and without staging, was described.

It may be mentioned that cantilevered shuttering was used in Britain for the construction of the river span, 150 ft. long, of a bridge at Aveley, over the river Severn, in the year 1936. Two side spans of 60 ft. served to counterweigh the central span during construction. The reinforcement was in 15-ft. lengths and the splices were staggered in groups at 5-ft. intervals, enabling 5 ft. of the bridge to be constructed at a time. No elaborate plant was used. There was a trolley on each cantilever from which the shuttering was suspended, but the greater part of the weight of the concrete was carried by the shuttering cantilevered off the

fixed shuttering behind. The suspended platform consisted of scaffold boards resting on the rungs of ladders hanging from the top. The cableway for moving the concrete and other materials was a discarded colliery rope suspended between trees on either side of the river, the motive power consisting of an old motor-car with the haulage rope passing around one of the back wheels from which the tyre was removed. A photograph of this work during construction is given above.

This work was fully described by Mr. A. P. Mason, B.Sc., M.I.C.E., and illustrated in "Concrete and Constructional Engineering" for August, 1937. The engineers were the British Reinforced Concrete Engineering Co., Ltd., and the contractors Messrs. Thomas Beighton, Ltd.

The Measurement of Humidity.

HUMIDITY of the atmosphere has to be controlled in many places and for many manufacturing processes, and a recent publication of the National Physical Laboratory, "Notes on Applied Science, No. 4—Measurement of Humidity" (H.M. Stationery Office. Price 1s.), out-


lines methods of measuring the moisture content of the air. The pamphlet describes the types of hygrometer required for precise and approximate measurements, explains the principles on which they work, and describes how to use and calibrate the instruments.

STEEL FORMS

The Multiple System of Interlocking

STEEL SHUTTERING

for in-situ concrete construction



**GUARANTEED HAND RIVETED CONSTRUCTION
THROUGHOUT**

ENORMOUS STRENGTH ALTHOUGH LIGHT IN WEIGHT

ENGINEERED WITH ACCURACY AND PRECISION

BUILT LIKE A SHIP FOR ENDURANCE

EACH UNIT A COMPLETE ASSEMBLY

NO LOOSE PARTS — LOW MAINTENANCE

POSITIVELY NO WELDING

YEARS OF HEAVY USAGE

A. A. BYRD AND CO., LIMITED

210, Terminal House, Grosvenor Gardens, London, S.W.1

'Phone: SLOane 5236.

'Grams: Byrdicom, Wesphone, London.

"Ritecure"

THE RIGHT CURE FOR CONCRETE

MEMBRANE CURING

for horizontal and vertical surfaces

"RITECURE"

MEMBRANE CURING

Further Notable Points

- RITECURE reacts with the calcium radical to aid in producing the tough, impervious, adherent film.
- RITECURE increases the abrasive resistance and ultimate durability of the concrete surface.
- RITECURE, colourless and non-staining, contains a temporary green indicator. This colour disappears in a day or two.



This illustration shows part of several miles of concrete kerbing on which "RITECURE" was used. Note the simple and one-man operation, and the absence of covering materials. This work was carried out by the County Council of the West Riding of Yorkshire. County Engineer: Mr. S. Maynard Lovell, O.B.E., T.D.

RITECURE is sprayed on the concrete surface and forms a cellophane-like skin which ensures the retention of the maximum amount of moisture in the concrete. It has been effectively and economically used on over eight million yards of roads, runways, floors, cooling towers, and other structures in this country and for many million yards of concrete abroad in extremely high and low temperatures and varying climatic conditions. Its use is backed by a highly skilled Technical Service with an extensive experience in concrete curing. For full details, send to:

STUART B. DICKENS, LTD.

99 VICTORIA STREET,
WORKS: OLD MILTON STREET,

LONDON, S.W.1.
LEICESTER.

TELEPHONE: ABBEY 4030
TELEPHONE: LEICESTER 20390

Reinforced Concrete Flats in South London.

At Clarence Avenue, Wandsworth, four six-story blocks of flats of reinforced concrete construction are being erected for the London County Council. Two of the blocks are 194 ft. long by 34 ft. wide and two are 154 ft. by 28 ft.; in each case the story-height from floor to floor is 8 ft. 6 in. and the height from the ground floor to the roof is 51 ft. One of the larger buildings contains 41 flats and the other 40 flats and a laundry; each

which in general are placed under the partitions. Both precast and in-situ beams are used and are supported either by the walls or by in-situ columns. The stair flights are precast and the landings cast in situ. The flat roofs are $4\frac{1}{2}$ in. thick and covered with a layer of sand $\frac{1}{2}$ in. thick, 2-in. hollow clay blocks, a 2-in. thickness of sand-cement mortar, and $\frac{3}{4}$ in. of asphalt. The sub-soil is clay and the foundations are generally



Fig. 1.—Tower Crane Hoisting a Shutter.

of the smaller buildings contains 34 flats. One of the larger blocks is shown in Fig. 1 during construction.

The structures comprise reinforced concrete load-carrying walls; the external walls are 7 in. thick and the party walls and walls surrounding the lift-wells and stair-wells are 6 in. thick. The partitions are of 2-in. clinker blocks. The $4\frac{1}{2}$ -in. floors are cast in situ, and where load-carrying walls do not occur the floors are supported by reinforced concrete beams

strip footings under the walls and rectangular bases under the columns.

The external walls are cast in outer shutters, one story high, comprising timber frames lined with plywood, and inner shutters of timber frames lined with wood-wool slabs which form an insulating face to the wall and were subsequently plastered. The outer faces are rendered with coloured cement mortar applied with a machine. Shutters for the ground-floor walls are shown in Fig. 2. The lengths of

the shutters are determined, having regard to the fenestration, so that there can be the greatest number of re-uses. Electrically-operated tower cranes travelling on a wide-gauge track are used to move the shutters from one position to another. These cranes have a reach of 65 ft. and a maximum lifting height of 120 ft. The walls are designed for a maximum stress of 760 lb. per square inch in direct compression and are reinforced with two layers of bars near each face. The vertical reinforcement comprises $\frac{3}{4}$ -in. bars at 12-in. centres, with extra bars horizontally over openings and short bars diagonally at the corners of openings.

Chimney stacks are in reinforced concrete and the flues are lined with fire-clay pipes fixed in the shuttering before the concrete is placed. Window and door frames are fixed by means of a "gun" (Fig. 4) which pierces the frame and drives a stud into the concrete, thus dispensing with wooden plugs and avoiding the difficulty of aligning the plugs with holes in the frames.

The precast beams are cast on the site in lengths which allow a gap of 1 in. between the ends of the beams and the supporting members. The ends of the beams are serrated and the reinforcement projects as shown in Fig. 3. The stair




Fig. 3.—Detail of Fixing Precast Beam.

flights are also cast on the site, with 7, 8, or 13 treads, on their sides, with reinforcement projecting at the ends. The precast beams and stairs are hoisted into position by the tower cranes and are propped until the concrete of the supporting members can support them. The floors and roofs are cast on extensible steel centres.

The concrete throughout the work is a 1 : 2 : 4 mixture with coarse aggregate of $\frac{3}{4}$ in. maximum size. The cement is delivered loose in vehicles carrying two cylindrical tanks, each with a capacity




Fig. 2.—Wall Shutters at Ground-floor Level.



Fig. 4.—Fixing Window Frames to Concrete Jambs.



STRONGER AND BETTER CONCRETE with the NEW

Winget 'VIBROCON' VIBRATING SPADE

13,000 Full Impulses per minute from
the Model 55

9,000 Full Impulses per minute from the
larger Model 70

On jobs demanding vibration methods the higher frequencies of Winget 'Vibrocon' Vibrating Spades give swifter compaction to maximum density. The workability of harsh mixes is increased and thorough consolidation can be achieved in 30 seconds. Use Model 70 (2½" dia.) for mass concrete and Model 55 (2.1/10" dia.) for closer reinforcement on smaller sections. There are no gears or belts and operation is extremely simple. Choice of three drives—Petrol, Electric or Pneumatic.

Greater strength. Greater density and homogeneity. Less shrinkage. Greater resistance to frost. Better bond between concrete and reinforcement. Better bond at construction joints.



Registered Trade Mark

Winget

CONTRACTORS' PLANT SPECIALISTS

WINGET LTD. ROCHESTER
Kent ENGLAND


Tel. Strand 7276 (3 lines) Telegrams: Wingetcon Rochester




SMITH'S

FIREPROOF FLOORS


The most adaptable System of
Suspended Hollow Concrete
Floor and Roof Construction
for large and small spans.



Showing uniform concrete soffit.
Obtained without use of slip tiles.



Showing Two-way Reinforce-
ment and Hollow Concrete
Blocks laid on Trianco Tele-
scopic Centers.



**2 WAY REINFORCED
SUSPENDED
CONCRETE FLOORS**

BUILDING EXHIBITION

Nov. 18th - Dec. 2nd
OLYMPIA - LONDON

STAND No. 294/5 Row P

The Two-way Reinforced Floor for
distribution of point loads with
efficiency and economy, employing the
original system of steel Telescopic
Centers.

Midland Associated Company & Licensees,
**PARKFIELD CONCRETE PRODUCTS
COMPANY LIMITED,**

St. Peter's Road, NETHERTON,

'Phone : Dudley 4315

SMITH'S FIREPROOF FLOORS LTD
IMBER COURT • EAST MOLESEY • SURREY
EMBerbrook 3300 (4 lines)




Fig. 5.—Discharging Loose Cement to Timber Silo.

of $2\frac{1}{2}$ tons, and is discharged by pneumatic pressure into timber silos with a capacity of about 18 tons (Fig. 5). A weigh-batching plant is used and the concrete is discharged from the mixers into skips which are hoisted by the tower cranes to the shutters.

It is anticipated that the four buildings will be completed by December, 1953; the superstructure of the first of the smaller buildings was completed in five months. The estimated cost of the four blocks is £294,200.

The aggregates, and also the loose cement and the cement silo, were supplied

by Messrs. Hall & Co., Ltd. The general contractors for the work are Messrs. Wates, Ltd.

The reinforced concrete was designed (to accord with plans and elevations supplied by the London County Council) by Mr. W. V. Zinn, B.Sc., M.I.C.E., in conformity with the London Building Act (Amendment Act), 1953. The contract is being carried out for the London County Council (Director of Housing and Valuer, Mr. Cyril H. Walker, O.B.E., M.C., F.R.I.C.S., F.R.I.B.A.; Architect of the Council, Dr. J. L. Martin, M.A., Ph.D., F.R.I.B.A.).

Films on Prestressed Concrete.

Two films on the Freyssinet system of prestressing have been made, and are available, with lecture notes, from Diana Wyllie Filmstrip Production, 18 Pont Street, London, S.W.1. One film deals

with the equipment and methods used in this system and the other describes the development and application of the system. The price of the films is £1 15s. each.

A Cylindrical Prestressed Concrete Tank.

A PRESTRESSED concrete tank described in a recent number of the French journal "La Technique Moderne" is stated to be the first constructed using a bonded wire system. The tank has a capacity of 772,000 gallons and is to be used for storing petrol.

The tank has an internal diameter of 78 ft. 9 in., the wall is 25 ft. 6 in. high with a thickness of 5.1 in., and the roof is a dome, 5.1 in. thick, with a rise of 7 ft. 10 in. The floor is 4½ in. thick and falls 1 in. in 8 ft. towards a central sump (Fig. 1). It was cast on a layer of plain concrete on about 2 ft. of compacted

horizontal and a vertical stress perpendicular to the radii of the tank. The rings are 4 ft. 3 in. high and each is designed to resist the pressure of water at a corresponding height. The concrete was cast in rings, of the same height as the meshes, in steel shutters supported by a structural steel frame. Each ring of mesh, except the lowest, is connected to the one below by 1-in. diameter bolts, the lowest ring being anchored by wire ties to the foundation beam. The prestressing force was applied to each mesh by 1½-in. diameter threaded rods attached to the top of the mesh and tensioned by




Fig. 1.—Cross Section through Tank.

sand. Around the perimeter of the floor, and retaining the sand, is a reinforced concrete beam 3 ft. 3 in. deep by 1 ft. 7½ in. wide which forms the foundation of the wall.

The floor is prestressed by 220 small-diameter wires, tensioned before casting the concrete, radiating from a steel ring surrounding the sump (Fig. 2) and anchored to the foundation beam. The floor was cast in one operation.

The Wall.


The wall is prestressed by six rings each comprising a diamond-shaped mesh of small diameter wires which follow the generating lines of a hyperbola within the inner third of the thickness of the wall, thus producing in the concrete a

bolts bearing on a horizontal steel member supported by the temporary steel frame (Fig. 3). There are 432 rods, each tensioned to 10 tons, creating in the concrete a circumferential compressive stress of 1140 lb. per square inch and a vertical compressive stress of 570 lb. per square inch. When the tank is filled these stresses are reduced to about 142 lb. per square inch.

The Dome.

The dome has to resist an internal pressure of 205 lb. per square foot and is prestressed. The dome was cast in two layers each about 2½ in. thick. After the first layer had hardened the prestressing wires were laid on its upper surface; these were, however, not tensioned until

Specialists in piling and pile driving plant



PRESTCORE

LARSEN

VIBRO

B.S.P. specialized piling systems comprise the following:—

PRESTCORE
Bored piles built up in place from pre-cast concrete units —can be formed without vibration (avoiding damage to adjacent buildings) and in limited headroom.

LARSEN
Steel sheet piling, for temporary cofferdams and permanent retaining walls, in docks and harbours, sea defence work, buildings and other structures.

VIBRO
Concrete piles cast-in-place to length required —ensuring a full cross-section of dense, compressed concrete.

PILE DRIVING PLANT
Designed and constructed for driving timber, steel and concrete piles of all types.

THE BRITISH STEEL PILING CO. LTD.
KINGS HOUSE, 10 HAYMARKET, LONDON, S.W.1

BSP

SHUTTERING by SGB



*Circular Column with
Mushroom Head*

SGB contract service covers:

Bills priced at Tendering Stage
MATERIALS & LABOUR supplied from
commencement of contract to completion

also SALE or HIRE:

TELECENTRES • SHUTTERING PLATES
PROPS • COLUMN CLAMPS • BEAM
CLAMPS • WALL BRACKETS

SCAFFOLDING (GREAT BRITAIN) LIMITED

MITCHAM, SURREY • Telephone: MITCHAM 3400 (21 lines) • Telegrams: SCAFCO, MITCHAM

Branches at: ABERDEEN • BIRMINGHAM • BOURNEMOUTH • BRIGHTON • BRISTOL
CAMBRIDGE • CARDIFF • DOVER • DUBLIN • DUNDEE • EDINBURGH • EXETER
GLASGOW • HULL • LEEDS • LIVERPOOL • MANCHESTER • NEWCASTLE • NOTTINGHAM
OXFORD • PLYMOUTH • PORTSMOUTH • SOUTHAMPTON • STOKE-ON-TRENT • SWANSEA

-the originators of tubular scaffolding!

Telephone your nearest
SGB Branch NOW!

after the tie-beam was constructed. The tie-beam was prestressed by 28 wires which were tensioned against the shutters, at 300 points around the circumference of the tie. After the concrete was cast the wires were released, creating an internal circumferential force of 100 tons in the




Fig. 2.—The Anchor for the Wires at the Sump.

beam. This was sufficient to resist the thrust due to the weight of the dome, the superimposed loads, and an internal suction equivalent to 41 lb. per square foot. Immediately the tie-beam was prestressed the wires in the dome were

tensioned and anchored to the part of the slab already cast, the second layer of concrete then being placed.




Fig. 3.—Bolts for Tensioning the Mesh in the Walls.

The quantities of material contained in the tank are: 347 cu. yd. of concrete, 12 tons of high-tensile steel, and 8 tons of mild steel. The tank, which is known as a "Weinberg" tank, was constructed by Entreprises Truchetet et Tansini.


Drawing-office Practice.

A REVISED edition has recently been published of the British Standard entitled "Drawing Office Practice for Architects and Builders" (No. 1192, 1953, price 7s. 6d. from the British Standards Institution). Recommendations are given on the sizes of drawings, drawing-boards, scales, methods of projection, numbering of drawings, the selection of tracing paper and cloth, and the reproduction of drawings. Lists of symbols and abbreviations are given with notes on hatching and colouring for the representation of materials.

Testing Stabilized Soils.

A BRITISH STANDARD entitled "Methods of Test for Stabilized Soils" (No. 1924, 1953, price 12s. 6d. from the British Standards Institution) contains details of tests for determining the moisture content, dry density, the relationship between the dry density and the moisture content, the unconfined compressive strength, and the cylinder-penetration ratio for soils that have been stabilized by controlling

the grading or by the addition of materials such as cement, lime, bitumen, resin, or aqueous solutions of chemicals. Methods for the preparation of samples for testing are also given. Different methods are described for testing fine-grained, medium-grained, and coarse-grained soils, and an appendix contains forms for recording and calculating the results of the tests.



Lectures on Prestressed Concrete.

A COURSE of lectures on prestressed concrete will be given at the London County Council Brixton School of Building on Wednesday evenings from October 7, 1953, to Easter, 1954, by Dr. P. W. Abeles and Mr. J. M. Jagger, and will include demonstrations. Tutorial classes in connection with the lectures will be held on Monday evenings commencing October 19. The fees are £3 5s. for the lecture course and £1 4s. for the tutorial course (£4 4s. for the two courses taken together). The courses are for those who have reached graduate standard in the theory of structures and are experienced in the design of reinforced concrete. Further particulars may be obtained from the Secretary of the School, Ferndale Road, London, S.W.4.

British Standards Institution.

THE address of the British Standards Institution is now 2 Park Street, London, W.1 (telephone Mayfair 9000).


Canadian Conference on Prestressed Concrete.

It is proposed to hold a conference on prestressed concrete in Toronto on January 28 and 29, 1954. Further information can be obtained from Mr. H. Fealdman, The Hydro-electric Power Commission of Ontario, 620 University Avenue, Toronto 2, Canada, who is the secretary of the organising committee.



High-pressure Production of Concrete BLOCKS

TRIANCO
No 'K' 2 Type
BLOCK MAKING MACHINE
*Power Operated
Fully Automatic*



This machine is specifically designed for the mass production of SOLID BLOCKS and is capable of producing 300 blocks per hour, which are jointed, compressed and extruded automatically. Fitments are also available for the manufacture of hollow blocks.

TRIANCO LIMITED
IMBER COURT, EAST MOLESEY, SURREY
Telephone: EMBerbrook 3300

Building Exhibition, Olympia.
Visit our Stands No. 294/5. Row P.

Full specification will be sent on application

Midland Associated Company & Licensees,
PARKFIELD CONCRETE PRODUCTS CO., LTD.,
St. Peter's Road, NETHERTON.
'Phone: Dudley 4315.

TRIANCO

BLOCK-MAKING MACHINES

MISCELLANEOUS ADVERTISEMENTS.

Situations Wanted, 3d. a word: minimum, 7s. 6d. Situations Vacant, 4d. a word: minimum 10s. Other miscellaneous advertisements, 4d. a word: 10s. minimum. Box number 1s. extra. The engagement of persons answering these advertisements is subject to the Notification of Vacancies Order, 1952.

Advertisements must reach this office by the 23rd of the month preceding publication.

SITUATIONS VACANT.

SITUATIONS VACANT. Reinforced concrete engineers require designer-draftsmen, preferably A.M.I.Struct.E., for work at Bristol or near London. Opportunity to widen experience. Good salary to right men. Box 3648, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

SITUATION VACANT. Old-established Tees-side firm requires section leader reinforced concrete designer-draftsman, fully experienced in designing and detailing reinforced concrete structures, foundations, and other civil work. Apply, giving full particulars and experience, quoting reference D, to Box No. 3656, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

SITUATION VACANT. Structural engineering assistant required in consulting engineer's office. Must be experienced and capable of designing and detailing reinforced concrete structures. Apply in writing, stating experience and salary required, to J. H. COOMBS & PARTNERS, Thames Corner, Sunbury-on-Thames.

SITUATIONS VACANT. Designer-draftsmen required for London office of well established reinforced concrete engineers. Experience in reinforced concrete frames, floors, roof and staircase construction essential. Progressive post. Pension scheme. Alternate Saturdays free. Write fully experience and salary required. Box 3675, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

SITUATIONS VACANT. Reinforced concrete designers and detailers, qualified men with at least five years' experience, required for drawing office of reinforced concrete specialists. Apply "TWISTLE" REINFORCEMENT, LTD., Alma Street, Southwick.

SITUATIONS VACANT. Clarke, Nicholls & Marcel, consulting engineers, require at their London office reinforced concrete designer-draftsman and draftsman-detailers. Permanent positions, interesting work. Apply in writing, stating age, experience, and salary required, to 21 Westbourne Grove, London, W.2.

SITUATION VACANT. Development engineer required by pre-cast concrete manufacturers for development of reinforced concrete and prestressed concrete products. Qualifications: civil engineering degree, knowledge of mechanical engineering, and practical experience on engineering contracts. Apply, giving details of education and experience, to MANAGING DIRECTOR, JOHN ELLIS & SONS, LTD., 21 New Walk, Leicester.

SITUATION VACANT. Assistant required by consulting engineers. Applicants must be experienced in reinforced concrete; knowledge of structural steelwork an advantage. Apply by letter, stating age, qualifications, and experience, to J. L. WHEELER & JUFF, Empire House, St. Martins le Grand, London, E.C.1.

SITUATION VACANT. Reinforced concrete detailer-draftsman, with minimum of three years' specialist experience, required. Apply, giving full particulars, to A. E. BEER, 96 St. George's Square, London, S.W.1. Telephone: Tate Gallery 9488.

SITUATIONS VACANT. THE TRUSSED CONCRETE STEEL CO., LTD., Truscon House, 35-41 Lower Marsh, London, S.E.1, have vacancies in the London Office for a senior designer, two designers, and three designer-detailers with considerable experience in reinforced concrete D.O. work. Five-days' week and pension scheme. Apply in writing to the above address, giving full particulars of age, education, and previous employment.

SITUATION VACANT. Experienced reinforced concrete designer required for work in the project section of a company of reinforced concrete engineers and contractors. Five-days' week and pension scheme. Write, giving full details of age, experience, and qualifications, to Box C.E. 578, c/o 191 Gresham House, London, E.C.2.

SITUATIONS VACANT. Consulting engineers require designer-draftsmen with experience in reinforced concrete work. Salary in accordance with qualifications and experience. Applicants should be Graduates of either the Institution of Civil or Structural Engineers. Apply in writing to ANDREWS, KENT & STONE, 60-66 Wardour Street, London, W.1.

SITUATION VACANT. Consulting structural engineer, Westminster, requires experienced reinforced concrete draughtsman-detailer. High salary and good prospects for suitable applicant. Write, stating age, qualifications, and full details of experience, Box 3679, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

SITUATION VACANT. Draughtsman with at least three years' experience in reinforced concrete detailing required immediately. Apply in writing only to PETER LIND & CO., LTD., Romney House, Tufton Street, Westminster, S.W.1, stating age, experience, and salary required.

SITUATIONS VACANT. The Port of London Authority invite applications for a number of positions as Civil Engineering Draftsmen at the following scales of pay, inclusive of pay supplement. The increments are annual, and commencing salaries within the scales are fixed according to qualifications and experience. (a) 1st Class: £602 10s. by £26 5s. to £731 15s. per annum. (b) 2nd Class: £528 by £22 to £71 per annum. (c) 3rd Class: £407 by £16 10s. to £440, then by £22 to £484 per annum. Applicants should have experience in the following:—For (a)—the design and detailing of reinforced concrete, steel, and timber structures. For (b) and (c)—detailing such structures with or without supervision. In all cases maritime works' experience and ability to make site surveys would be an advantage. Applications, giving age, experience, and indicating the position desired, to the ESTABLISHMENT OFFICER, PORT OF LONDON AUTHORITY, Trinity Square, London, E.C.3. Engagement is subject to the provisions of the Notification of Vacancies Orders, 1952.

SITUATION VACANT. Experienced engineer required for London office of reinforced concrete designers. Salary £1,000 p.a. or according to experience. Write, with particulars, to Box N. 462, c/o STREETS, 110 Old Broad Street, London, E.C.2.

SITUATION VACANT. Reinforced concrete engineers require section leader with first-class experience in the design of all types of reinforced concrete structures. The vacancy is in London. Five-days' week and pension scheme. Apply in writing, giving full particulars of age, experience, and qualifications, to Box C.E. 610, 191 Gresham House, London, E.C.2.

SITUATION VACANT. Young assistant to works manager required in concrete department, preferably with civil or structural engineering training. Apply in confidence, with details of previous experience and copies of references, to MANAGING DIRECTOR, THE CROFT GRANITE, BRICK & CONCRETE CO., LTD., Croft, Leics.

SITUATIONS VACANT. Two reinforced concrete detailer-draftsmen required for design office. Experience on multi-story frames or industrial structures an advantage. Write, giving particulars of age, experience, and salary required, to G. A. DODD & PARTNERS, 17-18 Railway Approach, London Bridge, London, S.E.1.

LINDSEY COUNTY COUNCIL, HIGHWAYS DEPARTMENT. Permanent Staff Vacancies: (1) BRIDGES ASSISTANT (2) ENGINEERING ASSISTANT. (1) Experience of bridge and structural design essential. Salary A.P.T. IV and V, starting on the appropriate step according to experience and qualifications. Graduate preferred but intermediate examination qualification may be accepted. (2) Experience in general engineering and surveying work. Salary A.P.T. IV and V, starting as for post (1). Intermediate examination qualification essential. N.J.C. service conditions. Applications, on forms obtainable from me, must be received by 23rd September, 1953. C. K. TALLACK, A.M.I.C.E., County Surveyor, County Offices, Newland, Lincoln.

(Continued on page 1881.)

MISCELLANEOUS ADVERTISEMENTS.

(Continued from page lxxi.)

SITUATION VACANT. Reinforced concrete draughtsman required in the civil engineering department of the Coppee Co. (Great Britain), Ltd., 140 Piccadilly, London, W.1. Work comprises colliery structures, bunkers, and tanks. Applicant also expected to assist in quantity surveying. Bonus and staff pension scheme in operation. Write stating age, experience, and salary required.

SITUATIONS VACANT. THE BRITISH REINFORCED CONCRETE ENGINEERING CO., LTD., have vacancies for detailers and designers within a salary range of £500 to £1,200 per annum, according to experience, in their Stafford and London offices. These appointments offer wide experience in the design of reinforced concrete, prestressed concrete, and shell structures. Staff pension scheme, five-days' week, and staff canteens. There are also vacancies in Bristol, Glasgow, and Newcastle-upon-Tyne.

SITUATION VACANT. Designer-draughtsman required by reinforced concrete specialists for their South-east Manchester office. Applicant must be capable of carrying out complete design and detailing of reinforced concrete structures with minimum supervision. A knowledge of prestressed concrete design and practice is desirable though not essential. Staff pension scheme. Reply giving full particulars including age and salary required. Box 3681, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

SITUATION VACANT. Assistant required in London professional office. Reinforced concrete design and detail experience essential. Knowledge of steelwork, prestressed concrete, and soil mechanics an advantage. A.M.I.C.E., A.M.I.Struct.E., and/or I.B.S. preferred. Varied projects with scope for initiative. Age limits 24/30. Five-days' week. Apply giving full particulars and salary required to Box 3682, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

SITUATIONS VACANT. Designers, draughtsmen, takers-off, and tracers required by hollow tile floor and reinforced concrete specialists in London, W.1. area. No age limit for candidates who can fill these positions satisfactorily. Write, giving details of experience, and salary required, to Box 3683, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

SITUATION VACANT. Senior engineer as manager for prominent South African reinforced concrete engineers. Qualified man with good personality and knowledge of structural engineering, and possessing business acumen, preferably with managerial experience, required for position offering good scope for advancement and carrying with it excellent remuneration according to ability and experience. Write giving fullest details to Box B210, JACKSON'S, 54 Old Broad Street, London, E.C.2.

PROFESSIONAL SERVICES.

PROFESSIONAL SERVICES. Reinforced concrete designer-draughtsman with 20 years' experience in the design of reinforced concrete structures, chemical plant, etc., undertakes to prepare complete designs, calculations, and working drawings to help consulting engineers. Excellent references. Moderate fee. Box 3684, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

FOR SALE.

FOR SALE. Concrete vibrators (pneumatic, electric, and petrol driven) for hire. CONTRACTORS SERVICES LTD., 65 Effra Road, London, S.W.2. Telephone: BRIXTON 4081.

FOR SALE. Steel plate to sizes, pressed sections, discs, and general metalwork. Keen prices and delivery. E. STEPHENS & SON LTD., Bath Street, London, E.C.1.

FOR SALE. Roadway sleepers at 8s. each. 30 ft. bull-head rails 80 lb. per yard at £18 per ton. Chaired sleepers, 12s. 6d. each at site. Delivered prices against specification. HOLMAN, Tolleshbury, Essex.

WANTED.

WANTED. Large quantities of mild steel rod in coils. From 7½ to 1 in. diameter. Any condition. Also coil ends. PIKE BROS., Colnbrook, Bucks. Telephone: Colnbrook 175.

WANTED. Copies of CONCRETE AND CONSTRUCTIONAL ENGINEERING for October, 1952, to May, 1953. Box 3680, CONCRETE AND CONSTRUCTIONAL ENGINEERING, 14 Dartmouth Street, London, S.W.1.

FOR HIRE.

FOR HIRE. Lattice steel erection masts (light and heavy), 30 ft. to 150 ft. high, for immediate hire. BELLMAN'S, Terminal House, London, S.W.1. Telephone: Sloane 5259.

ESTIMATING
PRECAST CONCRETE

A COMPLETE practical treatise on estimating and costing precast concrete, entitled "Estimating and Costing Precast Concrete Products and Cast Stone," by Mr. F. H. Fielder, Manager of Girling's Ferro-Concrete Co., Ltd. (Feltham), describes simplified methods based on the author's practice and long experience. Gives in handy form all the data necessary for estimating the cost of every type of precast concrete and cast stone unit, including the cost of materials, labour, overheads, and all other costs. 140 pages, 19" at a glance" tables of costs, 54 worked examples, 49 illustrations.

Price 7s. 6d. (by post 8s.).
175 dollars in Canada and U.S.A.

CONCRETE PUBLICATIONS LTD.
14 DARTMOUTH STREET, LONDON, S.W.1

Bound Volumes of
"Concrete and Constructional
Engineering."

BINDING cases for annual volumes of "Concrete and Constructional Engineering" can be supplied in cloth-covered boards lettered in gold on the spine with the title, volume number, and year of publication. Copies for binding should be sent post paid to Concrete Publications Ltd., 14 Dartmouth Street, London, S.W.1. Where possible, missing numbers will be supplied at the published price to make up incomplete sets, but as many of the numbers published during the past few years are not available it is advisable to ask the publishers whether they have the numbers required before sending incomplete sets. The cost of cloth-covered lettered cases is 5s. 3d. for each volume. The cost of supplying a case and binding a volume is 13s. 6d., including packing and carriage.



ALPHA CEMENT LTD


PORTLAND HOUSE, TOTHILL STREET

LONDON, S.W.1.

Telephone - Abbey 3456.

FRED MITCHELL & SON LIMITED

Building & Civil Engineering Contractors



*Bridge, Road and Rail Construction,
Cooling Towers, Silos & Commercial Buildings,
Excavations, Foundations, Piling,
Dock and Sea Defence Work,
Water Mains, Sewerage, Reservoirs etc.*

RIVER PLACE · CITY ROAD · MANCHESTER

Telephone: Central 7018/9